



INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH PUNE

(An Autonomous Institution of the Ministry of Education, Govt. of India)
Main Building, Gr floor, A block, Dr. Homi Bhaba Road, Pune-411 008.
Ph No 020 2590 8082 Fax 020 2588 7499 / 2589 8022

No : 54 (2) / IISER / Pune / 2021-22 / 66

Dated 09/03/2022

Notice Inviting Quotation

Sealed **NIQ** are hereby invited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to 3.00 PM 17/03/2022 from approved and eligible contractors registered with CPWD, Maharashtra state PWD, Railways, MES in appropriate category for electrical/ (B&C) works or supplier of said unit for the work mentioned below. The quotations will be opened at 3.30 PM on the same day.

Name of the work : Providing access control unit for G1 bird lab, lab no 306 at IISER Pune.

Issue to – Name and address of the agency :-

Terms and conditions:

- 1) The applicant should be registered with CPWD in western region, Maharashtra state PWD, MES, Railways in appropriate category for electrical / (B&C) works or supplier of said unit. The registration certificate should be valid till the last date of receipt of tender. Applicant should submit attested or notarized copies of the valid registration certificate along with quotation.
- 2) Time period for completion of work shall be 5 (Five) days from the date of placing the work order by IISER Pune. The act of backing out after quotation will debar such agencies for participating in future quotations of IISER Pune. Bidder may email queries on maintenance@iiserpune.ac.in or submit to IISER Pune office in hard copy on all working days before a day of submission date of quotation.
- 3) Quotation can be obtained from IISER Pune Engineering office at Main building between 10 am to 4 pm on all working days before date of submission. Applicant may quote by downloading quotation document from IISER Pune's website.
- 4) All agencies need to submit their quotation in hard copy in a sealed envelope to the office by suitable means on and before 3 pm on 17/03/2022. Quotation received after the date & time specified above shall not be accepted. Any delays, postal delay etc will be entertained. Agency should quote for all the items in the BOQ. The bid shall be submitted in the original Bid document (as issued by the IISER Pune) super scribing the name of work. Rates quoted in the words shall be treated as final for deciding L1 bidder.
- 5) Quotations will be opened on the same day (17/03/2022) at 3.30 pm in the presence of agency or their authored representative, if any. The offer of the agency should be commercially clear including acceptance of all terms and conditions of this quotations by the agency. IISER Pune reserves the right to accept or reject the quotations without assigning any reasons.
- 6) Quotations submitted with any conditions shall be treated as 'Conditional Quotation' and shall be summarily be rejected by IISER Pune.
- 7) Quoted rates should be inclusive of cost of all the material, labour cost, GST, all taxes, octroi, duties, cost of sample and fees towards testing of materials in labs , royalties etc. complete. Nothing extra shall be paid separately.

- 8) All approved make shall be as per list attached with this and as per CPWD and manufactures specifications. Agency should put up technical data and obtain prior approval on make of various material of IISER Pune before taking up work.
- The successful agency shall make his own arrangement for all tools and tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source. Agency should make own arrangement to safely tap of power from source to work location.
- No advance payment shall be made by IISER Pune.
- Quoted rates should be including GST, TDS and other applicable taxes and cess will be deducted from the bills of the work as applicable.
- 9) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications, manufactured specification & as per instruction of IISER Pune whenever specification CPWD / IS specification are not available.
- 10) The contractor shall ensure the minimum wages should be paid to the labors and employees in accordance with labour laws.
- 11) L1 Agency to submit actual measurement and abstract sheet to IISER Pune within 05 days from complete of work.


**Executive Engineer,
IISER Pune.**

Encl :

1. Schedule of Quantity – (BOQ) as per Annexure A



Sign & Stamp of the Agency :

Schedule of Quantity : annexure A

Date

Name of work : Providing access control unit for G1 bird lab, Lab no 306 at IISER Pune.

Item no	Description	Qty	Unit	Rate in (word & figure)	Amount
1	Supplying and drawing of UTP 4 pair CAT 6 LAN flexible cable in the existing surface / recessed steel / PVC conduit / casing capping as required.	5	M		
2	Supply and fixing of 25 mm PVC casing n capping on surface like wall/ partition / ceiling with required accessories like bends etc for existing data and power cable.	6	M		
3	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as required. 2 x 2.5 sqmm + 1 x 2.5 sqmm earth wire	6	M		
4	Supply, installation, testing and commissioning of double door Biometric control machine with software and other required accessories. ESSK K30 PRO Door Fingerprint Readers Access Control : TECHNICAL SPECIFICATIONS ; User Capacity: 2000, Fingerprints Capacity: 2000, Card Capacity: 2000, Transaction Storage: 100000, Push Data: Yes, Card Reader: Yes, Fingerprint sensor: 500 DPI Optical Sensor, FAR : <=0.0001% / FRR : <=1%, Identification Speed: <= 1sec , Algorithm Ver: 10, Display: 2.8" TFT Screen, Keypad: 4 x 4 Keypad, LED Indicator: Green/Red, Schedule Bell/Speaker: Mini Speaker, Communication: TCP/IP, USB-host , Standard Features: Inbuilt Battery Backup, Self Service Query, Status Switch, DST, T9 Input. Required software , programming for completion of work is in scope of agency.	1	No		
5	Supply, installation, testing and commissioning of Power Supply: 12V DC, 1.5 Amps, Operating Temperature: 0°C to 45°C, Operating Humidity: 20% - 80%, Dimension (in mm): 185 x 140 x 30, Access Control: Yes, Relay: 12V, Exit Readers: NO, Exit: NO TOUCH and PUSH BUTTON, Inbuilt Battery: yes, required wiring and termination etc.	1	No		
6	Supply, installation, testing & commissioning of double door electromagnetic lock with required accessories.	1	No		



7	Supply, installation, testing and commissioning of boltlock for electromagnetic lock with all accessories.	1	No		
8	Supply, installation, testing and commissioning of metal exit Push button switch with mounting box and required accessories	1	No		
9	supply , installation, testing and commissioning of Emergency Exist Switch (Green colour) with mounting box & required accessories.	1	No		
				(Rates quoted are all inclusive, nothing will be paid extra) Rs.Total	
				(In words Rs .	

Executive Engineer'

Akulkarni

