

No: 54(2) /IISER/Pune/2020-21/71

Date 22/3/2022

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to **3.00 PM on 29/3/2022** from eligible contractors registered with anyone CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite category (any one) for the work mentioned below. The quotations will be opened at 3.30 PM on the same day.

NAME OF WORK : PROVIDING AND FIXING EMERGENCY SHOWER AND EARTH WORK FOR PARKING AT PLOT BEHIND H CROSS AT IISER PUNE

Issue to –

Name and address of the agency –


Superintending Engineer

Terms and Conditions:

- 1) The applicant should be eligible contractors registered with anyone CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite. Applicant should submit self-attested valid Registration Certificate / Experience Certificate along with the quotation. Bidders not meeting the minimum eligibility criteria shall be summarily rejected.
- 2) Time period for completion of work shall be 1 (One) month from the date of placing the work order by IISER Pune. The act of backing-out after opening of quotation will debar such agencies for participating in the future quotations of IISER PUNE. Bidder may e-mail queries on maintenance@iiserpune.ac.in or submit to IISER PUNE office in hard copy on all working days one day before submission date of quotation as specified above.
- 3) Notice Inviting Quotation (NIQ) document may be obtained from IISER PUNE at 121, Engineering Section , Main Building, IISER PUNE Campus, Dr.Homi Bhabha Road, Pashan, Pune-411008 between 10 AM to 4 PM on all working days before date of submission. Applicant may submit quotation by obtaining NIQ document from IISER PUNE website at <http://www.iiserpune.ac.in/links/tender-notices-and-eoi>
- 4) All agencies need to submit their quotation in hard copy in sealed envelope containing by suitable means on and before **3 PM on** due date. Quotation received after the date & time specified above shall not be accepted. Any delays , postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ . Rates quoted in words shall be treated as Final for deciding L1 bidder. The bid shall be submitted in the original bid document (as issued by the IISER, Pune or Webcopy) super scribing the name of work. Quoted rates shall be valid for 60 days from the date of opening of quotations. Rates shall be quoted in hand writing in the spaces provided in NIQ document. Commercial envelopes of technically qualified bidders shall be opened accordingly. The offer of the agency should be commercially clear including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons. Engineer In-charge decision about item-wise or overall L1 bidder/s shall be final.

Sign & stamp of Agency-



NIQ : Page 1 of 3

- 5) Bids will be opened **on the same day at 3.30 PM** in the presence of agency or their authorized representatives, if any. Quotations submitted with any conditions shall be treated as conditional quotations and shall be summarily be rejected by IISER PUNE.
- 6) Quoted rates should be inclusive of cost of all the materials, labour cost , GST ,all taxes, royalties, cost of fuel, operator , octroi , duties , cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid separately. No, Bidder shall contact the IISER, Pune on any matter relating to his bid from the time of the bid opening to the time of issue of work order. Any effort by the Bidder to influence the IISER's bid evaluation, bid comparison or contract award decisions, may result in the rejection of his bid. Decision from competent authority/Engineer In-charge shall be final and binding to bidder in all the matters relating this work.
- 7) All approved makes shall be as specified in BOQ and as per CPWD specifications, agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work. The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location. Any scaffolding required shall be brought by contractor to complete the work with no cost to IISER Pune.
- 8) No advance payment shall be made by IISER Pune. Quoted rates should be including GST , TDS and other applicable taxes . Income Tax and labour cess will be deducted from the bills of the work.
- 9) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER PUNE whenever specification CPWD/ IS specification are not available.
- 10) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws. All the safety measures shall be followed by the L1 agency as per prescribed norms during execution of work with all the necessary safety tools etc. Executing Agency shall sole techno-commercially responsible for the strict adherence of safety norms and allied compensations etc.
- 11) Agency should submit measurements and abstract sheets to IISER PUNE for the payments within 30 days from completion of work.


Superintending Engineer

Encl : - Schedule of Quantity (BOQ) – As per Annexure A



ANNEX-A

NAME OF WORK : PROVIDING AND FIXING EMERGENCY SHOWER AND EARTH WORK FOR PARKING AT PLOT BEHIND H CROSS AT IISER PUNE.

Sr.No	Description of Item	Quantity	Unit	Rate	Amount
1	Full Body showers				
1.01	Supply and installation of SS 304 Safety shower and Twin cup Eye wash: Providing, supply, installation, testing and commissioning of emergency shower systems with twin cup eye showers, designed and engineered to secure easy operation. This allows for "one-action" activation of the shower system ensuring immediate and continued flushing without any need for further action. This easy operation also allows the injured person to use both hands to keep his eyes open for effective flushing, to undress under the shower or just to help exposing the affected area for better and more expedient treatment. On the eye shower the nozzles are protected by rubber cups to keep the injured person from hurting himself unintentionally. The nozzles are also protected against dust and dirt by the caps which are removed automatically by the initial jet of water. All eye showers & safety showers are delivered with water regulating devices ensuring 11.5 lit/min for eye wash and 75 lit/min for shower, constant adequate water flow regardless of high water pressure and to be fitted with backflow preventer. The rate is inclusive of the cost of all the materials and labour involved as per drawing and detailed specifications. Mode of measurement shall be in numbers .(Quoted rate shall be inclusive of all taxes, transportation, leads and lifts and nothing shall be paid extra on this account) Make :- Premier Polymer / Euronics / Unique	4	each		



2.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with GI clamps at 1.00 m spacing for good support to pipe. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. External work – below ground including excavation. Quoted rate shall be including material, labour, transportation, lead, lift, MTA, FTA, Tee, solvent cement, make holes in wall and making it good, GST etc complete. Nothing extra shall be paid separately. Length of pipe laid at site shall be measured for payments. Approved Make : Finolex/Supreme/Astral/Watertec				
2.01	32 mm nominal outer dia Pipes	150.00	meter		
2.02	25 mm dia outer dia Pipes	150.00	meter		
3.00	CPVC End caps				
3.01	32 mm nominal outer dia Pipes	4.00	each		
3.02	25 mm dia outer dia Pipes	4.00	each		
4.00	CPVC Reducing tee				
4.01	32mm-25mm-25mm confirming ASTM D2846	5.00	each		
4.02	32mm-25mm-32mm confirming ASTM D2846	5.00	each		
5.00	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) :				

5.01	32 mm nominal bore	5.00	each		
5.02	25 mm nominal bore with pipe barrel piece of 15mm for holding pipe	5.00	each		
6.00	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	1000.00	Per liter		
7.00	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge. Quoted rate shall be including GST , transportation , lead , lift , scaffolding etc complete. Nothing extra shall be paid separately.	50.00	sqm		
8.00	LEVELING WORK FOR PARKING				
8.01	Laying old cement concrete interlocking paver blocks of any design/shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer In-charge. (Old CC paver blocks shall be supplied by the department free of cost).	50.00	sqm		
8.02	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	100.00	cum		
8.03	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil	600.00	sqm		
8.04	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) : 6 graded stone aggregate 20 mm nominal size)	1.00	cum		

8.05	Brick work with clay flyash F.P.S. (non modular) brick of class designation 7.5 in superstructure above plinth level up to floor five level in : Cement mortar 1:4 (1 cement : 4 coarse sand) .	1.00	cum		
8.06	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	150.00	kg		
8.07	Structural steel work riveted, bolted or welded in built up sections, trusses , pipes , tubes and framed work or any MS material hollow tubes or structural steel , including cutting, hoisting, fixing , laying and joining of pipes in position and applying a priming coat of approved steel primer all complete. Material shall be recovered from existing structures/frames etc within campus as per instruction of Engineer In-charge.	400.00	kg		
	Total				



Superintending Engineer

[Signature]