

No: 54(2)/IISER/Pune/2020-21/74

Date 28/3/2022

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to **3.00 PM on 5/4/2022** from eligible contractors registered with anyone CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite category (any one) for the work mentioned below. The quotations will be opened at 3.30 PM on the same day.

NAME OF WORK : PROVIDING AND FIXING PLEATED SCREEN MOSQUITO NET AND WEATHER SHED FOR DAYCARE FACILITY AT IISER PUNE

Issue to –

Date of Submission extended to 25/4/22

Name and address of the agency –

[Signature]
Superintending Engineer

Terms and Conditions:

- 1) The applicant should be eligible contractors registered with anyone CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite or expert agency for mosquito net system. Applicant should submit self-attested valid Registration Certificate / Experience Certificate along with the quotation. Bidders not meeting the minimum eligibility criteria shall be summarily rejected.
- 2) Time period for completion of work shall be 1 (One) month from the date of placing the work order by IISER Pune. The act of backing-out after opening of quotation will debar such agencies for participating in the future quotations of IISER PUNE. Bidder may e-mail queries on maintenance@iiserpune.ac.in or submit to IISER PUNE office in hard copy on all working days one day before submission date of quotation as specified above.
- 3) Notice Inviting Quotation (NIQ) document may be obtained from IISER PUNE at 121, Engineering Section , Main Building, IISER PUNE Campus, Dr.Homi Bhabha Road, Pashan, Pune-411008 between 10 AM to 4 PM on all working days before date of submission. Applicant may submit quotation by obtaining NIQ document from IISER PUNE website at <http://www.iiserpune.ac.in/links/tender-notices-and-eoi>
- 4) All agencies need to submit their quotation in hard copy in sealed envelope containing by suitable means on and before **3 PM on** due date. Quotation received after the date & time specified above shall not be accepted. Any delays , postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ . Rates quoted in words shall be treated as Final for deciding L1 bidder. The bid shall be submitted in the original bid document (as issued by the IISER, Pune or Webcopy) super scribing the name of work. Quoted rates shall be valid for 60 days from the date of opening of quotations. Rates shall be quoted in hand writing in the spaces provided in NIQ document. Commercial envelops of technically qualified bidders shall be opened accordingly. The offer of the agency should be commercially clear including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons. Engineer In-charge decision about item-wise or overall L1 bidder/s shall be final.

Sign & stamp of Agency-



- 5) Bids will be opened **on the same day at 3.30 PM** in the presence of agency or their authorized representatives, if any. Quotations submitted with any conditions shall be treated as conditional quotations and shall be summarily be rejected by IISER PUNE.
- 6) Quoted rates should be inclusive of cost of all the materials, labour cost , GST ,all taxes, royalties, cost of fuel, operator , octroi , duties , cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid separately. No, Bidder shall contact the IISER, Pune on any matter relating to his bid from the time of the bid opening to the time of issue of work order. Any effort by the Bidder to influence the IISER's bid evaluation, bid comparison or contract award decisions, may result in the rejection of his bid. Decision from competent authority/Engineer In-charge shall be final and binding to bidder in all the matters relating this work.
- 7) All approved makes shall be as specified in BOQ and as per CPWD specifications, agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work. The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location. Any scaffolding required shall be brought by contractor to complete the work with no cost to IISER Pune.
- 8) No advance payment shall be made by IISER Pune. Quoted rates should be including GST , TDS and other applicable taxes . Income Tax and labour cess will be deducted from the bills of the work.
- 9) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER PUNE whenever specification CPWD/ IS specification are not available.
- 10) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws. All the safety measures shall be followed by the L1 agency as per prescribed norms during execution of work with all the necessary safety tools etc. Executing Agency shall be sole techno-commercially responsible for the strict adherence of safety norms and allied compensations etc.
- 11) Agency should submit measurements and abstract sheets to IISER PUNE for the payments within 30 days from completion of work.


Superintending Engineer

Encl : - Schedule of Quantity (BOQ) – As per Annexure A



NAME OF WORK : PROVIDING AND FIXING MOSQUITO NET AND WEATHER SHED FOR DAYCARE FACILITY AT IISER PUNE.

Sr.	Description	Qty.	Unit	Rate in words and figures	Amount
1	Weather Shed work				
1.1	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes. (Rate including of all taxes, GST, Material , labour , insurance, safety precaution, etc nothing extra shall be payable.)	150.00	Kg		
1.2	Providing & fixing Sky light roofing Polycarbonate Multi wall sheet 10mm thick tuflite / Lexan make of approved colour & approved sample including curvature a sper drawing. Sheet shall be fixed on existing MS frame work with required shape anodized extruded section both side with EPDM Gaskets, baker rod, nut & bolts, waster etc complete .After fixing sheet gaps shall be filled with heavy duty DOW weather proof silicone sealant 688 Grade DOW or equivalent make with adhesive removable abro tape both side with all safety , labour insurance, all complete as per approved drawing & direction of Engineer-in-Charge. Upto 5mm depth and 5 mm width.(Rate including of all taxes, wastage, GST, material, labour scaffolding, Cleaning site after work, etc complete.)	20.00	Sqm		
1.3	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work. (Rate including of all taxes, GST, Material , labour , insurance, safety precaution, etc nothing extra shall be payable.)	20.00	Sqm		



2	Pleated insect screen system				
2.01	<p>Providing & fixing pleated insect screen system for existing UPVC balcony doors consisting of around framing of aluminium (minimum 60 micron powder coated white colour) extruded aluminium sections of size 25mm x 25mm for vertical section, 25mmx40mm for top section and 25mm x 25mm for bottom section compatible for pleated screen system made of imported fibre glass mesh or 100% polyester and resistant to UV, Salt water and up to 2nd category for wind complete as per manufacturer specifications. The screen shall get collapse on one side of the frame and operates on polyester thread with filament core on tension based technology. Locking shall be provided with permanent rubber magnets for sturdy and easy locking fixed on the powder coated vertical style. Bidder shall refer to the reference image provided along with the tender . Rate shall be inclusive of cost of all the materials, labour & operations involved, factory manufacturing and fixing at site with existing PVC frame, all taxes, LBT etc. complete. For payment out to out screen system including aluminium frame for screen system fixed at site shall be measured for working out the area for payment.</p> <p>Approved Makes Phifer/ Meshworkz / Radius Corp/ Moskill</p>	475.00	sqft		
Total Amount					



[Signature]
Superintending Engineer