

No: 54(2) /IISER/Pune/2022-23/ 87

Date 20/4/2022

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to **3.00 PM on 27/4/2022** from eligible contractors registered with anyone CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite category (any one) for the work mentioned below. The quotations will be opened at 3.30 PM on the same day.

NAME OF WORK : CLEANING OF STORM WATER DRAINS AT IISER PUNE.

Issue to –

Name and address of the agency –

Terms and Conditions:


Superintending Engineer
INDIAN INSTITUTE OF SCIENCE
EDUCATION & RESEARCH PUNE
CE, Main Building, Engineering Section,
Dr. Homi Bhabha Road, Pune-08.

- 1) The applicant should be eligible contractors registered with anyone CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite. Applicant should submit self-attested valid Registration Certificate / Experience Certificate along with the quotation. Bidders not meeting the minimum eligibility criteria shall be summarily rejected.
- 2) Time period for completion of work shall be 1 (One) month from the date of placing the work order by IISER Pune. The act of backing-out after opening of quotation will debar such agencies for participating in the future quotations of IISER PUNE. Bidder may e-mail queries on maintenance@iiserpune.ac.in or submit to IISER PUNE office in hard copy on all working days one day before submission date of quotation as specified above.
- 3) Notice Inviting Quotation (NIQ) document may be obtained from IISER PUNE at 121, Engineering Section , Main Building, IISER PUNE Campus, Dr.Homi Bhabha Road, Pashan, Pune-411008 between 10 AM to 4 PM on all working days before date of submission. Applicant may submit quotation by obtaining NIQ document from IISER PUNE website at <http://www.iiserpune.ac.in/links/tender-notices-and-eoi>
- 4) All agencies need to submit their quotation in hard copy in sealed envelope containing by suitable means on and before **3 PM on** due date. Quotation received after the date & time specified above shall not be accepted. Any delays , postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ . Rates quoted in words shall be treated as Final for deciding L1 bidder. The bid shall be submitted in the original bid document (as issued by the IISER, Pune or Webcopy) super scribing the name of work. Quoted rates shall be valid for 60 days from the date of opening of quotations. Rates shall be quoted in hand writing in the spaces provided in NIQ document. Commercial envelopes of technically qualified bidders shall be opened accordingly. The offer of the agency should be commercially clear including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons. Engineer In-charge decision about item-wise or overall L1 bidder/s shall be final.

Sign & stamp of Agency-



- 5) Bids will be opened **on the same day at 3.30 PM** in the presence of agency or their authorized representatives, if any. Quotations submitted with any conditions shall be treated as conditional quotations and shall be summarily be rejected by IISER PUNE.
- 6) Quoted rates should be inclusive of cost of all the materials, labour cost , GST ,all taxes, royalties, cost of fuel, operator , octroi , duties , cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid separately. No, Bidder shall contact the IISER, Pune on any matter relating to his bid from the time of the bid opening to the time of issue of work order. Any effort by the Bidder to influence the IISER's bid evaluation, bid comparison or contract award decisions, may result in the rejection of his bid. Decision from competent authority/Engineer In-charge shall be final and binding to bidder in all the matters relating this work.
- 7) All approved makes shall be as specified in BOQ and as per CPWD specifications, agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work. The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location. Any scaffolding required shall be brought by contractor to complete the work with no cost to IISER Pune.
- 8) No advance payment shall be made by IISER Pune. Quoted rates should be including GST , TDS and other applicable taxes . Income Tax and labour cess will be deducted from the bills of the work.
- 9) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER PUNE whenever specification CPWD/ IS specification are not available.
- 10) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws. All the safety measures shall be followed by the L1 agency as per prescribed norms during execution of work with all the necessary safety tools etc. Executing Agency shall sole techno-commercially responsible for the strict adherence of safety norms and allied compensations etc.
- 11) Agency should submit measurements and abstract sheets to IISER PUNE for the payments within 30 days from completion of work.


 Superintending Engineer
 INDIAN INSTITUTE OF SCIENCE
 EDUCATION & RESEARCH PUNE
 GF, Main Building, Engineering Section,
 Dr. Homi Bhabha Road, Pune-08.

Encl : - Schedule of Quantity (BOQ) – As per Annexure A

Sign		
Revised Date of submission		
Call	Call-2	Call-3

Sign & stamp of Agency-



NAME OF WORK : CLEANING OF STORM WATER DRAINS AT IISER PUNE.

ANNEX-A : BILL OF QUANTITY

Sr No	Description of item	Quantity	Unit	Rate in words and figures	Amount
1	Manual cleaning of box type RCC storm water drain of size 1500mm/1000mm X 1500mm or hume pipes of any diameter by removing debris , soil , sediment grit , construction waste, bricks , scrap material , wooden waste material etc as per site conditions including dewatering wherever required . Work shall be done by manually without damaging drain , with all necessary safety harness , duct ventilation fans , safety helmets and masks , safety ropes and nets etc. complete. Quoted rate shall be including removal of chamber covers , removal and re-fixing of interlocking pavers above chamber covers , cleaning of walls , floor and ceiling of duct , removal of debris , shifting and dumping at approved location within campus as approved by Engineer In-charge, IISER Pune. Agency shall deploy professional team proficient with the cleaning of drain system , any object obstructing flow shall be cleaned from floor of drain system. Quoted rate shall be including of all taxes,duties GST, insurance , tools , cost towards shifting of debris , dewatering, safety harness etc complete . Nothing extra shall be payable separately. Actual length of storm water drain cleaned after disposal of debris shall be measured for payments.	1,500.00	meter		
2	Cleaning of existing gravel filter media of Rain Water Filtration system at IISER Pune campus by batch-wise removing and lifting of sand media , cleaning , drying , stacking as per size of media and relaying inside filtration chamber and desilting chamber. Quoted rate shall be including cleaning of walls of filtration chamber, water entry chamber , collection chamber. Water for cleaning will be provided by IISER Pune free of cost at one point , agency to tap from source by own flexible pipe. Silt shall be collected at one location and disposed within campus as per the direction of Engineer In-charge. Quote rate shall be cost of cleaning , desilting , lead and lift of the media , removal of cement pipes , relaying of pipes , cleaning of Geofabric , GST etc complete. Nothing extra shall be paid separately. Volume of media cleaned shall be measured for payments.	50.00	cum		
				Total	



Superintending Engineer
INDIAN INSTITUTE OF SCIENCE
PUNE
Superintending Engineer
Dr. Homi Bhabha Road, Pune-411 008.