



INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH PUNE

(An Autonomous Institution, Ministry of Education Department, Govt. of India)
IISER Pune Campus, Dr. Homi Bhaba Road, Pune-411 008.
Ph. No 020 2590 8001 Fax 020 2588 7499 / 2589 8022

No: 54(2) /IISER/Pune/22-23/ 159

Dated 14/ 06 / 2022

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to **3.00 PM on 20/06/2020** from approved and eligible contractors registered with CPWD, Maharashtra State PWD, Railways, MES in appropriate category for electrical/ (B&C) works for the work mentioned below. The quotations will be opened at 3.30 PM on the same day.

Name of work: - Providing Electrical distribution for G1 lab, Frog facility and Chemistry Gr fl meeting room, IISER Pune

Issue to –

Name and address of the agency –

Terms and Conditions:

- 1) The applicant should be registered (**ANY ONE**) with CPWD in western region, Maharashtra State PWD, MES, Railways in appropriate category for electrical / (B & C) works. The registration certificate should be valid till the last date of receipt of tender. Applicant should submit attested or notarized copies of the valid registration certificate and work completion certificate along with quotation.
- 2) Time period for completion of work shall be **30 (Thirty)** days from the date of placing the work order by IISER Pune. The act of backing-out after quotation will debar such agencies for participating in future quotations of IISER PUNE. Bidder may e-mail queries on maintenance@iiserpune.ac.in or submit to IISER PUNE office in hard copy on all working days before a day of submission date of quotation.
- 3) Quotation can be obtained from IISER PUNE Engineering office at Main Building between 10 AM to 4 PM on all working days before date of submission. Applicant may quote by downloading quotation document from IISER PUNE website.
- 4) All agencies need to submit their quotation in hard copy in a sealed envelope to this office by suitable means on and before **3 PM on 20/06/2022**. Quotation received after the date & time specified above shall not be accepted. Any delays, postal delay etc. will not be entertained. Agency should quote for all the items in the BOQ. The bid shall be submitted in the original Bid document (as issued by the IISER, Pune) super scribing the name of work. Rates quoted in the words shall be treated as final for deciding L1 bidder.
- 5) Quotations will be opened on the same day (**20/06/2022**) at **3.30 PM** in the presence of agency or their authorized representatives, if any. The offer of the agency should be commercially clear



including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons.

- 6) Quotations submitted with any conditions shall be treated as 'Conditional Quotation' and shall be summarily be rejected by IISER PUNE.
- 7) Quoted rates should be inclusive of cost of all the materials, labour cost , GST , all taxes, octroi, duties, cost of sample and fees towards testing of materials in labs, royalties etc. complete. Nothing extra shall be paid separately.
- 8) All approved makes shall be as per list attached with this and as per CPWD and manufactures specifications. Agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work.

The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location.

No advance payment shall be made by IISER Pune.

Quoted rates should be including GST, TDS and other applicable taxes and cess will be deducted from the bills of the work as applicable.

- 9) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications, manufactured specification & as per instruction of IISER PUNE whenever specification CPWD/ IS specification are not available.
- 10) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws.
- 11) L1 Agency to submit actual measurements and abstract sheet to IISER PUNE within 30 days from completion of work.


Superintending Engineer,
IISER Pune

Encl: - 1. Schedule of Quantity

2. Approved Make list for electrical

Sign & stamp of Agency-



APPROVED MAKELIST FOR ELECTRICAL		
S.No.	Material	IISER PUNE Make
1	Instrument Transformers Indicating Meters	Kappa/Kalpa/Voltamp
2	Analog	Meco/Rishab/AE/HPL
3	Digital	Meco/AE/ Socomec/Conzerv/SECURE/HPL
4	Indicating Lamps	GE/SCHNEIDER/ Teknic/L&T/ALTOS, (MULTIPLE LEDs)
5	PLC / Digital Load Monitor / Power monitor	Electrex/Allen Bradley/GE/Schneider/Conzerv
6	Panel Accessories / Terminal block	Dirak/Elmax/phoenix/Wago
7	Timers	L& T/Minilec/ Siemens/ GE/ Schneider
8	TVSS	ASCO /Schneider/ABB
9	Cable Terminating Kits	Raychem Heat Shrinkable/3M/CCI
10	Earthing	Erico/Nimbus/Ashlok
11	MV Switch Boards (LT panels)	Accusonic /Load Controls /Elins / Lotus Switchgear / Pace Switch gears/ Suvarna Electricals
12	Moulded Case Circuit Breaker	GE (Spectra / Record)/Schneider (COMPACT)/ L & T (O SINE)/ABB/MDS Legrand
13	MCB Distribution Board	Legrand/Schneider /Siemens
14	Miniature Circuit Breaker	MK/Legrand /Siemens/Schneider
15	ELCB / RCBO	MK/Legrand /Siemens/Schneider
16	Earth Leakage Relay	MK/Legrand /Siemens/Schneider
17	LT Cables (XLPE)	Polycab/Finolex/CCI



18	PVC Insulated copper wire FRLS	Polycab/Finolex/CCI
19	Cable Glands	Dowells/SMI/CCI/Electrowerke
20	PVC Rigid conduits	Precision/DIAMOND/Finolex/Polycab
21	M S Conduits	BEC/BI,
22	Switches, Sockets, Plug etc	Legrand Mosaic/MK/Schneider/ Anchor(Ave)
23	Ceiling rose / HOLDERS	Legrand Mosaic/MK/Schneider/ Anchor(Ave)
24	Light fitting, Flourscent CFL/GLs	Philips / Wipro/ GE
25	LED Light fitting	Wipro/Asian/Siska /Philips
26	Ceiling Fan	Crompton greaves (high breeze)/ Bajaj Super Model /Usha
27	Exhaust Fans	Alstom/Almonard/Usha/CGL
28	Telephone Cables	Delton/Finolex/ Polycab
29	Telephone Sockets	Anchor /MK (Suitable to mount on Legrand DLP trunking) /
30	Terminal Junction boxes	Elmex
31	Power Socket Industrial type	Legrand Mosaic/Mk/Schneider,
32	TV Outlet	Anchor/Legrand/MK
33	Cable trays	Storrax/ Skaber/Profab
34	Metallic raceways	Storrax/ Skaber/Profab
35	PVC raceways / PVC DLP trucking	LEGRAND/ MK/Schneider
36	Aluminium raceways	LEGRAND/ MK/Schneider
37	Surface / Recess mounted FTL fixtures	Philips/Wipro/GE
38	Recess mounted down lighter	Philips/Wipro/GE
39	Wall mounted luminaire	Philips/Wipro/GE
40	Data Cable - CAT-6	D-Link/Legrand/Polycab
41	External light fittings/ Garden Light fittings	Philips/Wipro /GE/Philips
42	Base plates and face plates	Legrand Mosaic/ MK/Schneider/Anchor

43	Full loaded patch panels	D link or RR
44	Data patch cords	D link or RR
45	Fire Alarm Control Panel	Notifier / Edward / Bosch / Cooper / Siemens
46	Repeater Panel	Notifier / Edward / Bosch / Cooper / Siemens
47	Addressable Smoke Detector	Notifier / Edward / Bosch / Cooper / Siemens
48	Addressable Multi Sensor Detector	Notifier / Edward / Bosch / Cooper / Siemens
49	Addressable Heat Detector	Notifier / Edward / Bosch / Cooper / Siemens
50	Addressable Strobe Cum Sounder	Notifier / Edward / Bosch / Cooper / Siemens
51	Addressable Sounder / Hooter	Notifier / Edward / Bosch / Cooper / Siemens
52	Addressable Manual Call point	Notifier / Edward / Bosch / Cooper / Siemens
53	Addressable Monitor Module	Notifier / Edward / Bosch / Cooper / Siemens
54	Addressable Control Module	Notifier / Edward / Bosch / Cooper / Siemens
55	FRLS Armoured Cable	Finolex / Polycab / Lapp
56	Other Items	Approval of Engineer In charge.
57	Isolation Transformer	Numeric Digital system (Novature)/ Neelkanth power solution/Ador powertrans



BOQ (Scheduled Of Quantity)

Name of work : Providing Electrical distribution for G1 lab, Frog facility and Chemistry Gr fl meeting room, IISER Pune

Please Note that Quoted rates are inclusive of all taxes, labor, transportation etc. Nothing Extra shall be paid separately.

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Rates in words and Figure	Amount
1	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. 15/16 A switch	3	Each		
2	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. 16 A socket	3	Each		
3	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. 6 A switch	11	Each		
4	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. 6 A socket	11	Each		
5	Supply, Installation, Testing & Commissioning of single UTP CAT6 I/O of specified make with different colours for differentiating Data, Voice & Wifi and other services inclusive of termination of UTP CAT6 cable at each I/O as required as per drawing. The IO shall be mounted inside simplex or duplex or quad faceplate as applicable and using suitable backbox assembly. It shall be as per technical specifications with all the necessary mounting accessories as required for complete installation.	5	Each		
6	Supplying and fixing following Modular base & cover plate (Clip on support for mounting switches etc) on existing DLP U PVC trunking etc. as required. 4 module 85 mm	12	Nos		
7	Supplying and fixing following Modular base & cover plate (Clip on support for mounting switches etc) on existing DLP U PVC trunking etc. as required. 1 module 85 mm	5	Nos		



8	Supplying and fixing modular blanking plate on the existing modular plate & switch box excluding modular plate as required.	6	Each		
9	Supply & installation of surface mounted DLP U- PVC adaptable trunking raceways, fabricated out of U-PVC to Off-White or approved shade as per IS 733 of thickness 2.0mm for the base and sides with removable covers, complete with necessary bends, suitable sized junction boxes, internal angle, external angle, flat 90 degree angle , end caps , seperators and tees etc, Complete. (For every 1mtr distance cable tag has to be provided for each circuit in the raceways - as more that 1C FRLS copper wire is required for 1 Circuit) PVC RACEWAYS (Along the wall), DLP U- PVC adaptable trunking . Size: 105x 50mm PVC Raceways for Power & Data with above specifications	22	Meter		
10	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 12 way (12), Double door	2	Each		
11	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. 2 X 4 sq. mm + 1 X 4 sq. mm earth wire	100	Meter		
12	Supply of Following size of PVC insulated and PVC sheathed power cable of 1.1 KV grade. 4 C x 10 sq.mm Cu. Conductor multistand armoured cable, quoted rates shall be including all taxes,duties,royalties,lead,lift,transportation,GST etc complete.Nothing shall be payable separately. Work shall be executed as per direction of engineer in charge,IISER Pune. Actual cable laid at site shall be measured for payments.	100	Meter		



13	Supply of Following size of PVC insulated and PVC sheathed power cable of 1.1 KV grade. 1 C x 10 sq.mm Cu. Conductor multistand flexible cable, quoted rates shall be including all taxes,duties,royalties,lead,lift,transportation,GST etc complete.Nothing shall be payable separately. Work shall be executed as per direction of engineer in charge,IISER Pune. Actual cable laid at site shall be measured for payments.	100	Meter		
14	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole	10	Each		
15	Supplying and fixing following rating, double pole, (single phase and neutral), 240 V, residual current circuit breaker (RCCB), having a sensitivity current 30 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required. 25 A	2	Each		
16	Supplying and making end termination with brass compression gland and copper lugs for following size of PVC insulated and PVC sheathed / XLPE copper conductor cable of 1.1 KV grade as required. 4 x 10 sq. mm	6	Each		
17	Supplying and fixing 30 A, 240 V, SPN Industrial type socket outlet, with 2 pole and earth, metal enclosed plug top alongwith 30 A "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required.	3	nos		
18	Supplying and fixing 30 A, 415 V, TPN Industrial type socket outlet, with 4 pole and earth, metal enclosed plug top alongwith 30 A "C" curve, TPMCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required.	1	nos		
19	Supplying and drawing of UTP 4 pair CAT 6 LAN Cable in the existing surface/ recessed Steel/ PVC conduit as required. 1 run of cable	470	Meter		



20	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required. 25 mm	150	Meter		
	Total (Including all)				

Sign and Stamp of Agency


 Superintending Engineer

