

शुद्धिपत्र

**CORRIGENDUM**

**कार्य का नाम: आईआईएसईआर पुणे में व्याख्यान कक्ष परिसर भवन में वॉटरप्रूफिंग का कार्य।**  
**NAME OF WORK : WATERPROOFING WORKS AT LECTURE HALL COMPLEX BUILDING AT IISER PUNE.**

**NIT No. : 31/IISER/PUNE/2024-25**

विषय: बीओक्यू में 'कार्य के नाम' में संशोधन

**SUBJECT : REVISION IN THE BOQ SPECIFICATIONS AND UNIT OF MEASUREMENTS**

निविदा की बीओक्यू में निर्दिष्ट 'कार्य का नाम' संलग्न शुद्धिपत्र के अनुसार संशोधित किया गया है। बोलीदाताओं से अनुरोध है कि वे इसका ध्यान रखें और तदनुसार बोली लगाएँ।

'Name of work' specified in the BOQ of the tender is stand modified as per appended corrigendum.  
Bidders are requested to take note of it and quote accordingly.

शुद्धिपत्र / CORRIGENDUM		
Page No	टेंडर के अनुसार / As per Tender	संशोधित / Revised
<b>PDF Tender Document</b> Volume No-3, BOQ ( PDF document Page No-250-251)	1. Unit of Measurement of Item No 1.01 is Nos 2. Unit of Measurement of Item No 1.02 is Nos 3. Unit of Measurement of Item No 1.03 is Nos 4. Unit of Measurement of Item No 1.04 is Nos	1. Unit of Measurement of Item No 1.01 stands modified to <b>Sqm</b> 2. Unit of Measurement of Item No 1.02 is stands modified to <b>Sqm</b> 3. Unit of Measurement of Item No 1.03 is stands modified to <b>Sqm</b> 4. Unit of Measurement of Item No 1.04 is stands modified to <b>Sqm</b> No change in quantity of work.
<b>PDF Tender Document</b> Volume No-3, BOQ Item No-1.03 ( PDF document Page No-251) <b>And</b> <b>Excel BOQ document</b> Item No-1.03	Repairs of existing thermostatic flooring tiles by removing existing Broeken chipped tiles, hoi ow portions below tiles removed portion , including removing of existing unserviceable/cracked tiles , disposing of debris at approved dumping ground within campus etc complete as per instruction of Engineer In-charge , etc complete. Quoted rate shall be including GST , transportation , lead , lift .wastage, scaffolding etc complete. Nothing extra shall be paid separately Actual area of tiles removed shall be measured for payments.	Stands modified to 'Repairs of existing thermostatic/vitrified flooring tiles at terrace by removing existing broken chipped tiles, the hollow portions below tiles to be removed along the tile and filling mortar with Dr.Fixit waterproofing compound in <b>CM 1:6</b> till the height to match the level of surrounding floor with neat cement coat at top. Quoted rate shall be including of removing of existing unserviceable/cracked tiles , disposing of debris at approved dumping ground within campus etc complete as per instruction of Engineer In-charge , etc complete. Quoted rate shall be excluding GST and including transportation , lead , lift .wastage, scaffolding etc complete. Nothing extra shall be paid separately. Actual area of tiles repaired at site shall be measured for payments.  No Change in the unit and quantity of the item.



*Handwritten signature/initials*

<b>PDF Tender Document</b> Volume No-3, BOQ Item No-1.04 ( PDF document Page No-251) <b>And</b> <b>Excel BOQ document</b> Item No-1.04	Filling of acrylic elastic property mortar in the gaps of Thermo-resistant flooring tiles/walls at Terrace with Factory made paste from Sika cracksil Acrylic paste / Dr.fixit crack-X paste / Dulux Aquatech crack filler upto elasticity property of 20mm (ready to use paste) prepare surface by cleaning and applying Dr. Fixit primeseal & making sure that crack is totally filled up tooling the surface to obtain an even smooth finish including curing of the cracks . Quoted rate shall be including working at inaccessible location etc complete. Quoted rate shall be including GST , transportation , lead , lift , scaffolding etc complete. Nothing extra shall be paid separately. Approved Makes Nerolac/Dulux/Asian	Filling of acrylic elastic property mortar in the cracks of walls with factory made paste from Sika cracksil Acrylic paste / Dr.fixit crack-X paste / Dulux Aquatech crack filler/Asian Crack fill up to elasticity property of 20mm (ready to use paste) prepare surface by cleaning and applying Dr. Fixit prime-seal & making sure that crack is totally filled up tooling the surface to obtain an even smooth finish including curing of the cracks . Quoted rate shall be including working at inaccessible location etc complete. Quoted rate shall be excluding GST and including transportation , lead , lift , scaffolding etc complete. Nothing extra shall be paid separately. Approved Makes Nerolac/Dulux/Asian/Sikha/Dr.Fixit No Change in unit and quantity of item.
---	---	---

बोलीदाता को ई-प्रोक्चोरमेंट पोर्टल पर इस शुद्धिपत्र के संदर्भ में बोली जमा करनी होगी।

निविदा शर्तों, मात्रा, इकाई, बीओक्यू मद के विवरण में कोई परिवर्तन नहीं।

बोलीदाताओं से अनुरोध है कि वे इस पर ध्यान दें और तदनुसार बोली लगाएं।

Bidder to submit the bid with reference to this corrigendum on E-procurement portal.

No change in the tender conditions and quantity of the BOQ item.

Bidder are requested take note of it and quote accordingly.

जारी करने की तिथि: 12.12.2024

Date of Issue : 12.12.2024

अधीक्षण अभियंता  
Superintending Engineer,  
आईआईएसईआर पुणे  
IISER Pune

