

भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान पुणे
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH PUNE

डॉ. होमी भाभा मार्ग, पुणे 411008, महाराष्ट्र, भारत | Dr. Homi Bhabha Road, Pune 411008, Maharashtra, India
T +91 20 2590 8001 W www.iiserpune.ac.in



No: 54(2) /IISER/Pune/2025-26/ 98

Dated 26-08-2025

कोटेशन आमंत्रित करने की सूचना
NOTICE INVITING QUOTATION

निदेशक, आईआईएसईआर, पुणे की ओर से अधोहस्ताक्षरी द्वारा नीचे उल्लिखित कार्यों के लिए 02/09/2025 को अपराह्न 3:00 बजे तक, सीपीडब्ल्यूडी, महाराष्ट्र राज्य लोक निर्माण विभाग, रेलवे और एमईएस में से किसी एक के साथ पंजीकृत अनुमोदित और पात्र ठेकेदारों से विद्युत (बी एंड सी) कार्यों के लिए या विभिन्न प्रकार के पंपों की आपूर्ति, स्थापना, परीक्षण और कमीशनिंग के क्षेत्र में विशेषज्ञ एजेंसी से मुहरबंद कोटेशन आमंत्रित किए जाते हैं। पंजीकरण प्रमाणपत्र निविदा प्राप्ति की अंतिम तिथि तक वैध होना चाहिए। कोटेशन उसी दिन अपराह्न 3:30 बजे खोले जाएंगे।

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to 3.00 PM on **02/09/2025** from approved and eligible contractors registered with anyone of CPWD, Maharashtra State PWD, Railways, and MES in appropriate category for electrical (B&C) works or expert agency in the field of supply, installation, testing and commissioning of various types of pump. The Registration Certificate should be valid till the last date of receipt of tender. The quotations will be opened at 3.30 PM on the same day.

कार्य का नाम: एसटीपी प्लांट, आईआईएसईआर पुणे में विभिन्न प्रकार के पंपों का प्रतिस्थापन।

इसे दे दो -

एजेंसी का नाम, पता और ईमेल आईडी

Name of work: Replacement of various types of pump at STP plant, IISER Pune.

Issue to -

Name address and email id of the agency -

नियम और शर्तें:

Terms and Conditions:

Sign & Stamp of Agency

नोट - हिंदी और अंग्रेजी संस्करण के बीच किसी भी विवाद के मामले में अंग्रेजी संस्करण प्राथमिक होगा।
Note - In case of any discrepancies between Hindi and English version, English version shall prevail.



Handwritten signature

कार्य का नाम: एसटीपी प्लांट, आईआईएसईआर पुणे में विभिन्न प्रकार के पंपों का प्रतिस्थापन।
Name of work: Replacement of various types of pump at STP plant, IISER Pune.

१. आवेदक को सीपीडब्ल्यूडी, महाराष्ट्र राज्य लोक निर्माण विभाग, रेलवे, एमईएस में से किसी एक के साथ विद्युत (बी एंड सी) कार्यों के लिए उपयुक्त श्रेणी में पंजीकृत अनुमोदित और योग्य ठेकेदार होना चाहिए, या विभिन्न प्रकार के पंपों की आपूर्ति, स्थापना, परीक्षण और कमीशनिंग के क्षेत्र में विशेषज्ञ एजेंसी होना चाहिए। आवेदक को ग्राहक विभाग से पिछले तीन वर्षों के भीतर पूर्ण किए गए कार्य के अनुभव प्रमाण पत्र की सत्यापित या नोटरीकृत प्रतियाँ और कार्य समाप्ति प्रमाण पत्र की प्रति कोटेशन के साथ जमा करनी होंगी। न्यूनतम पात्रता मानदंडों को पूरा न करने वाले बोलीदाताओं को सरसरी तौर पर अस्वीकार कर दिया जाएगा।
२. कार्य पूरा करने की समयावधि आईआईएसईआर पुणे द्वारा कार्य आदेश देने की तिथि से 30 होगी। कोटेशन आउट का कार्य ऐसी एजेंसियों को आईआईएसईआर पुणे के भविष्य के कोटेशन में भाग-खोलने के बाद बैक लेने से वंचित कर देगा। बोलीदाता maintenance@iiserpune.ac.in पर प्रश्न ई मेल कर सकते हैं या- उपरोक्त निर्दिष्ट कोटेशन की तारीख जमा करने से एक दिन पहले सभी कार्य दिवसों पर हार्ड कॉपी में आईआईएसईआर पुणे कार्यालय में जमा कर सकते हैं।
३. नोटिस आमंत्रण 121 दस्तावेज आईआईएसईआर पुणे से (एनआईक्यू), इंजीनियरिंग अनुभाग, मुख्य भवन, आईआईएसईआर पुणे परिसर, डॉ होमी भाभा रोड, पाषाण, पुणे 411008 -में सभी कार्य दिवसों से पहले सुबह बजे के बीच प्राप्त किया जा सकता है। प्रस्तुत करने की तारीख। आवेदक 4 बजे से शाम 10 आईआईएसईआर पुणे की वेबसाइट <http://www.iiserpune.ac.in/links/tender-notice-and-eoi> से एनआईक्यू दस्तावेज प्राप्त करके कोटेशन जमा कर सकते हैं।
४. सभी एजेंसियों को अपने उद्धरण हार्ड कॉपी में एक सीलबंद लिफाफे में जमा करने की आवश्यकता है, जिसमें दो अलग-अलग लिफाफे हों, एक लिफाफे में खंड 1 में उल्लिखित योग्यता दस्तावेज हों और दूसरे लिफाफे में हस्ताक्षर, स्टॉप, एनआईक्यू दस्तावेज उद्धृत दरों के साथ इस कार्यालय को उपयुक्त माध्यम से जमा करने की अंतिम तिथि और समय से पहले। ऊपर निर्दिष्ट तिथि और समय के बाद प्राप्त उद्धरण स्वीकार नहीं किए जाएंगे। किसी भी देरी, डाक देरी आदि पर विचार नहीं किया जाएगा। एजेंसी को बीओक्यू में सभी वस्तुओं के लिए उद्धरण देना चाहिए। बोली मूल बोली दस्तावेज (जैसा कि आईआईएसईआर, पुणे द्वारा जारी किया गया है) में काम का नाम लिखते हुए प्रस्तुत किया जाना चाहिए। शब्दों में उद्धृत दरों को एल 1 बोलीदाता तय करने के लिए अंतिम माना जाएगा। उद्धरण उसी दिन (02/09/2025) को दोपहर 3.30 बजे एजेंसी या उनके अधिकृत प्रतिनिधियों की उपस्थिति में खोले जाएंगे
५. कोटेशन उसी दिन अपराह्न बजे एजेंसी या उनके अधिकृत प्रतिनिधियों 3.30, यदि कोई हो, की उपस्थिति में खोली जाएगी। एजेंसी का प्रस्ताव व्यावसायिक रूप से स्पष्ट होना चाहिए जिसमें एजेंसी द्वारा इस कोटेशन के

Sign & Stamp of Agency

नोट:- हिंदी और अंग्रेजी संस्करण के बीच किसी भी विवेक के मामले में, अंग्रेजी संस्करण प्राथमिक होगा।
Note - In case of any discrepancies between Hindi and English version, English version shall prevail.



Handwritten signature in blue ink.

कार्य का नाम: एसटीपी प्लांट, आईआईएसईआर पुणे में विभिन्न प्रकार के पंपों का प्रतिस्थापन।
Name of work: Replacement of various types of pump at STP plant, IISER Pune.

५. कोटेशन उसी दिन अपराह्न बजे एजेंसी या उनके अधिकृत प्रतिनिधियों 3.30, यदि कोई हो, की उपस्थिति में खोली जाएगी। एजेंसी का प्रस्ताव व्यावसायिक रूप से स्पष्ट होना चाहिए जिसमें एजेंसी द्वारा इस कोटेशन के सभी नियमों और शर्तों की स्वीकृति शामिल है। आईआईएसईआर पुणे बिना कोई कारण बताए कोटेशन को स्वीकार या अस्वीकार करने का अधिकार सुरक्षित रखता है
६. किसी भी शर्त के साथ जमा किए गए कोटेशन को सशर्त कोटेशन माना जाएगा और आईआईएसईआर पुणे द्वारा सरसरी तौर पर खारिज कर दिया जाएगा।
७. उद्धृत दरों में सभी सामग्रियों की लागत, श्रम लागत, जीएसटी, सभी कर, चुंगी, शुल्क, नमूने की लागत और प्रयोगशालाओं में सामग्री के परीक्षण के लिए शुल्क, रॉयल्टी आदि शामिल होना चाहिए। अतिरिक्त कुछ भी अलग से भुगतान नहीं किया जाएगा। नहीं, बोलीदाता अपनी बोली से संबंधित किसी भी मामले में बोली खुलने के समय से कार्य आदेश जारी करने के समय तक आईआईएसईआर, पुणे से संपर्क करेगा। बोलीदाता द्वारा आईआईएसईआर के बोली मूल्यांकन, बोली तुलना या अनुबंध पुरस्कार निर्णयों को प्रभावित करने के किसी भी प्रयास के परिणामस्वरूप उसकी बोली को अस्वीकार किया जा सकता है।
८. सभी स्वीकृत निर्माण बीओक्यू में निर्दिष्ट के अनुसार होंगे और सीपीडब्ल्यूडी विनिर्देशों के अनुसार, एजेंसी को तकनीकी डेटा डालना चाहिए और काम शुरू करने से पहले आईआईएसईआर पुणे की विभिन्न सामग्रियों के निर्माण पर पूर्व अनुमोदन प्राप्त करना चाहिए। सफल एजेंसी कार्य पूरा होने के मद्देनजर कार्य आदि के लिए सभी उपकरण और टैकल की अपनी व्यवस्था स्वयं करेगी। एजेंसी को एक स्रोत पर बिजली निःशुल्क उपलब्ध कराई जाएगी, एजेंसी को स्रोत से कार्य स्थल तक सुरक्षित रूप से बिजली के दोहन की व्यवस्था स्वयं करनी चाहिए। आईआईएसईआर पुणे द्वारा कोई अग्रिम भुगतान नहीं किया जाएगा। उद्धृत दरों में जीएसटी, टीडीएस और अन्य लागू कर शामिल होने चाहिए। काम के बिल से इनकम टैक्स और लेबर सेस की कटौती की जाएगी।
९. बीओक्यू नवीनतम सीपीडब्ल्यूडी विनिर्देश, आईएस विनिर्देशों और आईआईएसईआर पुणे के निर्देश के अनुसार जब भी सीपीडब्ल्यूडी आईएस विनिर्देश उपलब्ध नहीं हैं /, के अनुसार किए जाने वाले कार्य के लिए विशिष्टता।
१०. ठेकेदार यह सुनिश्चित करेगा कि श्रमिकों और कर्मचारियों को श्रम कानूनों के अनुसार न्यूनतम मजदूरी का भुगतान किया जाए। सभी आवश्यक सुरक्षा उपकरणों आदि के साथ कार्य के निष्पादन के दौरान निर्धारित मानदंडों के अनुसार एल एजेंसी द्वारा मापी गई सभी सुरक्षा का पालन किया जाएगा। निष्पादन एजेंसी सुरक्षा 1

Sign & Stamp of Agency

नोट:- हिंदी और अंग्रेजी संस्करण के बीच किसी भी विषयवस्तु के मामले में, अंग्रेजी संस्करण प्राथमिक होगा।
Note - In case of any discrepancy between Hindi and English version, English version shall prevail.



710

कार्य का नाम: एसटीपी प्लांट, आईआईएसईआर पुणे में विभिन्न प्रकार के पंपों का प्रतिस्थापन।
Name of work: Replacement of various types of pump at STP plant, IISER Pune.

११. एजेंसी को प्रत्येक तिमाही के भुगतान के लिए माप और सार पत्रक प्रत्येक तिमाही के पूरा होने से 30 दिनों के भीतर विवरण के साथ आईआईएसईआर पुणे को प्रस्तुत करना होगा।
१२. एजेंसी को कार्य के निष्पादन के दौरान सभी सुरक्षा उपायों का पालन करना चाहिए, कोई भी दुर्घटना एजेंसी के दायरे में होगी।

1. The applicant should be approved and eligible contractors registered with anyone of CPWD, Maharashtra State PWD, Railways, MES in appropriate category for electrical (B&C) works **OR** expert agency in the field of supply, installation, testing and commissioning of various types of pump. Applicant should submit attested or notarized copies of the experience certificate for the work completed within last three years from client department with copy of completion certificate to along with the quotation. Bidders not meeting the minimum eligibility criteria shall be summarily rejected.
2. Time period for completion of work shall be 30 days from the date of placing the work order by IISER Pune. The act of backing-out after opening of quotation will debar such agencies for participating in the future quotations of IISER PUNE. Bidder may e-mail queries on maintenance@iiserpune.ac.in or submit to IISER PUNE office in hard copy on all working days one day before submission date of quotation as specified above.
3. Notice Inviting Quotation (NIQ) document may be obtained from IISER PUNE at 121, Engineering Section, Main Building, IISER PUNE Campus, Dr. Homi Bhabha Road, Pashan, Pune - 411008 between 10 AM to 4 PM on all working days before date of submission. Applicant may submit quotation by obtaining NIQ document from IISER PUNE website at <http://www.iiserpune.ac.in/links/tender-notices-and-eoi>
4. All agencies need to submit their quotation in hard copy in a sealed envelope containing two separate envelopes, one envelope containing qualification documents mention in Clause 1 and second envelope containing sign, Stamp, NIQ documents with quoted rates to this office by suitable means on and before last date and time of submission. Quotation received after the date & time specified above shall not be accepted. Any delays, postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ.

Sign & Stamp of Agency

नोट:- हिंदी और अंग्रेजी संस्करण के बीच किसी भी विषमता के मामले में, अंग्रेजी संस्करण प्रचलित रहेगा।
Note - In case of any discrepancies between Hindi and English version, English version shall prevail.



कार्य का नाम: एसटीपी प्लांट, आईआईएसईआर पुणे में विभिन्न प्रकार के पंपों का प्रतिस्थापन।
Name of work: Replacement of various types of pump at STP plant, IISER Pune.

received after the date & time specified above shall not be accepted. Any delays, postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ. The bid shall be submitted in the original Bid document (as issued by the IISER, Pune) super scribing the name of work. Rates quoted in the words shall be treated as final for deciding L1 bidder. Quotations will be opened on the same day **(02/09/2025) at 3.30 PM** in the presence of agency or their authorized representatives, if any. Please mentioned – **Technical /Qualification bid** on envelope-1 and **Financial Bid** on envelope - 2.

5. Quotations will be opened on the same day at 3.30 PM in the presence of agency or their authorized representatives, if any. The offer of the agency should be commercially clear including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons.
6. Quotations submitted with any conditions shall be treated as conditional quotations and shall be summarily be rejected by IISER PUNE.
7. Quoted rates should be inclusive of cost of all the materials, labour cost, GST, all taxes, octroi, duties, cost of sample and fees towards testing of materials in labs, royalties etc. complete. Nothing extra shall be paid separately. No, Bidder shall contact the IISER, Pune on any matter relating to his bid from the time of the bid opening to the time of issue of work order. Any effort by the Bidder to influence the IISER's bid evaluation, bid comparison or contract award decisions, may result in the rejection of his bid.
8. All approved makes shall be as specified in BOQ and as per CPWD specifications, agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work. The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location. No advance payment shall be made by IISER Pune. Quoted rates should be including GST, TDS and other applicable taxes. Income Tax and labour cess will be deducted from the bills of the work.

Sign & Stamp of Agency

नोट:- हिंदी और अंग्रेजी संस्करण के बीच किसी भी विसंगति के मामले में, अंग्रेजी संस्करण सत्य माना जाएगा।
Note - In case of any discrepancies between Hindi and English version, English version shall prevail.



THP

कार्य का नाम: एसटीपी प्लांट, आईआईएसईआर पुणे में विभिन्न प्रकार के पंपों का प्रतिस्थापन।
Name of work: Replacement of various types of pump at STP plant, IISER Pune.

9. Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER PUNE whenever specification CPWD/ IS specification is not available.
10. The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws. All the safety measures shall be followed by the L1 agency as per prescribed norms during execution of work with all the necessary safety tools etc. Executing Agency shall be solely techno-commercially responsible for the strict adherence of safety norms and allied compensations etc.
11. Agency should submit measurements and abstract sheets to IISER PUNE for the payments for each quarter with details within 30 days from completion of each quarter.
12. The agency should follow all safety measures during the execution of the work, any mishap happen will be on scope of Agency.

अधीक्षण अभियंता
आईआईएसईआर पुणे
Superintending Engineer
IISER Pune

Sign & Stamp of Agency

नोट - हिंदी और अंग्रेजी संस्करण के बीच किसी भी विरोधाभास के मामले में अंग्रेजी संस्करण में।
Note - In case of any discrepancies between Hindi and English version English version shall prevail.



Date :26-08-2025

BOQ

Name of work : Supply and replacement of horizontal type open well submerciable pumps for UG Sump at ISER Pune.Year 2024-25

Item no	Description	Qty	Unit	Rate	amount in Rs.
A	B	C	D	E	F=CxE
1	Supply of surface mounted Monoblocok type 15 HP, , 8-50 meter head range, 440 V, 3 phase AC, output deliver size 80x65 mm , Discharge 28 to 6 lps, with minimum one year warranty. Make Deccan / Kirloskar / CG	1	Nos	71000	71000
2	Supply of surface mounted Monoblocok type 10 HP, , 8-42 meter head range, 440 V, 3 phase AC, output deliver size 80x65 mm , Discharge 28 to 6 lps, with minimum one year warranty. Make Deccan / Kirloskar / CG	2	Nos	58000	116000
3	Supply of surface mounted Monoblocok type 5 HP, , 6-24 meter head range, 440 V, 3 phase AC, output deliver size 80x80 mm , Discharge 20 to2 lps, with minimum one year warranty. Make Deccan / Kirloskar / CG	2	Nos	42000	84000
4	Supply of surface mounted Monoblocok type 1 HP, , 6-16 meter head range, 440 V, 3 phase AC, output deliver size 80x80 mm , Discharge 20 to2 lps, with minimum one year warranty. Make Deccan / Kirloskar / CG	2	Nos	12700	25400
5	Supply and installation of Fully automatic Star Delta starter for 15 HP Pump with required accessories, VM, AM indication lamp, push buttons as complete with timer, contactor, relay and internal wiring etc. Installation of wall surface with required mounting accessories. Make L&T / Siemens / Schindler	1	Nos	16000	16000
6	Supply and installation of Fully automatic Star Delta starter for 10 HP Pump with required accessories, VM, AM indication lamp, push buttons as complete with timer, contactor, relay and internal wiring etc. Installation of wall surface with required mounting accessories. Make L&T / Siemens / Schindler	2	Nos	12700	25400
7	Supply and installation of DOL starter for 5 HP Pump with required accessories, push buttons as complete with timer, contactor,Overload relay and internal wiring etc. Installation of wall surface with required mounting accessories. Make L&T / Siemens / Schindler	2	Nos	5000	10000



BOQ

Name of work : Supply and replacement of horizontal type open well submerciable pumps for UG Sump at IISER Pune. Year 2024-25

Item no	Description	Qty	Unit	Rate	amount in Rs.
A	B	C	D	E	F=CxE
8	Supply and installation of DOL starter for 1 HP Pump with required accessories, push buttons as complete with timer, contactor, Overload relay and internal wiring etc. Installation of wall surface with required mounting accessories. Make L&T / Siemens / Schindler	2	Nos	3000	6000
9	Installation, testing and commissioning of Existing horizontal type, 15 HP, 440 V, 3 phase AC, . Installation will be done into existing UG sump (depth upto 5 m). Work includes labour, crane, supporting nylon ropes from three sides, waterproof joints on cables, plumbing work for pipe connection, hardwares, tools , supervision etc., as complete.	1	Nos	5000	5000
10	Installation, testing and commissioning of Existing horizontal type, 10 HP, 440 V, 3 phase AC. Installation will be done into existing UG sump (depth upto 5 m). Work includes labour, crane, supporting nylon ropes from three sides, waterproof joints on cables, plumbing work for pipe connection, hardwares, tools , supervision etc., as complete.	2	Nos	3500	7000
11	Installation, testing and commissioning of Existing horizontal type, 5 HP, 440 V, 3 phase AC. Installation will be done into existing UG sump (depth upto 5 m). Work includes labour, crane, supporting nylon ropes from three sides, waterproof joints on cables, plumbing work for pipe connection, hardwares, tools , supervision etc., as complete.	2	Nos	2750	5500
12	Installation, testing and commissioning of Existing horizontal type, 01 HP, 440 V, 3 phase AC. Installation will be done into existing UG sump (depth upto 5 m). Work includes labour, crane, supporting nylon ropes from three sides, waterproof joints on cables, plumbing work for pipe connection, hardwares, tools , supervision etc., as complete.	2	Nos	2000	4000



BOQ

Name of work : Supply and replacement of horizontal type open well submerciable pumps for UG Sump at IISER Pune.Year 2024-25

Item no	Description	Qty	Unit	Rate	amount in Rs.
A	B	C	D	E	F=CxE
13	Supplying LT cable having copper conductor XLPE insulated sheathed,galvanised steel tape armoured cable with pvc outer sheathing 1.1 KV (Confirming to IS 7098 Part-II amended upto date as per the following sizes). Including the cost of all materials, labour, Handling of materials of equipment and machineries all lead lift, loading and unloading, transportation, if any other incidental charges at all level complete all as per specification and as directed by Engineer-in charge. 4 Core X 4 sqmm copper armoured cable	60	meter	264	15840
14	Supply and laying of 3 C x 4 sqmm copper flex flat cable , 1100 V grade, PVC insulated for connecting pump to starter as complete.	100	meter	170	17000
15	Supplying, fixing, testing and commissioning of butterfly valve of PN 1.6 rating with bronze/gunmetal seat duly ISI marked complete with nuts, bolts, washers, gaskets conforming to IS 13095 of following sizes as required : 40 mm	6	set	3591	21546
16	Providing, installation, testing and commissioning of non-return valve of following sizes confirming to IS: 5312 complete with rubber gasket, GI bolts, nuts, washers etc.as required :50mm	2	set	5790	11580
17	Providing, installation, testing and commissioning of non-return valve of following sizes confirming to IS: 5312 complete with rubber gasket, GI bolts, nuts, washers etc.as required :65mm	1	set	6418	6418
18	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required. Upto 35 sq. mm	10	mtr	387	3870
19	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.: Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	2	cum	1200	2400



Handwritten signature/initials in blue ink.

BOQ						
Name of work : Supply and replacement of horizontal type open well submerciabale pumps for UG Sump at IISER Pune.Year 2024-25						
Item no	Description	Qty	Unit	Rate	amount in Rs.	
A	B	C	D	E	F=CxE	
20	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1-1½:3 (1 Cement: 1½ coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size)	2	cum	7000	14000	
Total in words :Four Lakhs Sixty-seven Thousand Nine Hundred Fifty-four Rupees Only		Total Estimated amount(Inclusive of all taxes)		4,67,954.00		
कुल राशि पर उद्धृत की जाने वाली प्रतिशत दर यहां चित्र और शब्दों में दी गई है (जीएसटी सहित)		अंकों में /In Figures :(ABOVE / BELOW) (TICK APPLICABLE).....% on Total Estimated amount				
PERCENTAGE RATE TO BE QUOTED ON TOTAL AMOUNT HERE IN FIGURE AND WORDS		शब्दों में /In Words : (ABOVE / BELOW) (TICK APPLICABLE).....% on Total Estimated amount				
स्थिति / STATUS		ABOVE / BELOW (TICK APPLICABLE)(ON TOTAL AMOUNT)				
उद्धृत प्रतिशत के साथ कुल राशि (जीएसटी सहित)						
TOTAL AMOUNT WITH QUOTED PERCENTAGE (Including GST) IN WORDS						
TOTAL AMOUNT WITH QUOTED PERCENTAGE (Including GST) IN FIGURE						



Superintending Engineer
IISER Pune

