

Corrigendum1

Date 16/03/2026


Subject: Reply to bidder queries

Please refer below mentioned IISER Pune reply to bidders queries.

Sr. No	Bidders' queries	IISER Reply	Remark
1	In BoQ, Basic amount and total amount column shown same amount. Please clarify.	Bidder please note, updated BoQ is uploaded on CPP portal. Copy of same is attached herewith.	

निविदा शर्तों, बीओक्यू के आइटम विनिर्देश में कोई बदलाव नहीं। बोलीदाता से अनुरोध है कि इसे नोट करें और तदनुसार बोली लगाएं।

No change in terms and conditions, item specification of BOQ. Bidder are requested take note of it and quote accordingly.


अधीक्षण अभियंता
Superintending Engineer,
आईआईएसईआर पुणे
IISER Pune

Tender Inviting Authority: Director-IISER Pune

Name of Work: Providing 100KVA UPS for G1 Lab 312 IISER Pune

Contract No.: NIT No. :39/IISER/Pune/2025-26

Sl. No.	Item Description	Quantity	Units	Estimated Rate excluding GST in P	TOTAL AMOUNT Excluding GST	TOTAL AMOUNT In Words excluding GST
1	Bidder Please note that quoted rate are inclusive of transportation, labour, royalties taxes etc. except GST. GST will be paid as Govt of India, rules and regulation.	3	4	5	54	7
2	Supply installation testing and commissioning Online UPS- Input supply: Three Phase, Output supply: Three Phase. Supplying, Installation, Testing & Commissioning of 100 KVA UPS, as per specifications attached as Annexure A	1	Nos	1082175.42	1082175.42	INR Ten Lakh Eighty Two Thousand One Hundred & Seventy Five and Paise Forty Two Only
3	Supplying LT cable having copper conductor XLPE insulated sheathed, galvanized steel tape unarmoured cable with pvc outer sheathing 1.1 KV class (Conforming to IS 7098 Part-II amended upto date as per the following sizes), including the cost of all materials, labour , Handling of materials of equipment and machineries all lead lift, loading and unloading, transportation, if any other incidental charges at all level complete all as per specification and as directed by Engineer-in-charge. 3.5 Core x 120 Sqmm FRLS Heavy Duty armoured aluminium Cable.	100	RMt	1694.92	169492.00	INR One Lakh Sixty Nine Thousand Four Hundred & Ninety Two Only
4	Supplying LT cable having copper conductor XLPE insulated sheathed, galvanized steel tape unarmoured cable with pvc outer sheathing 1.1 KV class (Conforming to IS 7098 Part-II amended upto date as per the following sizes), including the cost of all materials, labour , Handling of materials of equipment and machineries all lead lift, loading and unloading, transportation, if any other incidental charges at all level complete all as per specification and as directed by Engineer-in-charge. 1 Core x 120 Sqmm FRLS Heavy Duty unarmoured flexible Copper Cable.	100	RMt	2457.63	245763.00	INR Two Lakh Forty Five Thousand Seven Hundred & Thirty Three Only
5	Supplying LT cable having copper conductor XLPE insulated sheathed, galvanized steel tape unarmoured cable with pvc outer sheathing 1.1 KV class (Conforming to IS 7098 Part-II amended upto date as per the following sizes), including the cost of all materials, labour , Handling of materials of equipment and machineries all lead lift, loading and unloading, transportation, if any other incidental charges at all level complete all as per specification and as directed by Engineer-in-charge. 1 Core x 70 Sqmm FRLS Heavy Duty unarmoured Copper (CuV) Cable.	200	RMt	1440.88	288136.00	INR Two Lakh Eighty Eight Thousand One Hundred & Thirty Six Only
6	Supply installation, testing and commissioning of Chemical earthing using electrode of size 76 mm minimum diameter, minimum 03 meter long and connected with 50x5 mm copper internal strip, material of construction COPPER, complete with existing excavation / bore, civil work for chamber, cast iron cover size 450 x 450 mm, with backfill compound as required to fill earth pit up to mark, the earth resistance shall be as per IS 3043 (Approved make : Vash earthing / True Power / Fast Electrode / Maxwell Earthing)	3	Set	21641.53	64924.59	INR Sixty Four Thousand Nine Hundred & Twenty Four and Paise Fity Nine Only

PRICE SCHEDULE

(The BOD template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Reserved Values only)

7	Providing boring / drilling bore well of 150mm dia for casing / strainer pipe, by suitable method, including drilling in all strata, including hiring & running charges of all equipments, tools, plants and machineries required for the job, all complete as per direction of Engineer in charge.	12	Meter	847.46	10169.52	INR Ten Thousand One Hundred & Sixty Nine and Paise Fifty Two Only
8	Supplying fixing and wiring MCCB Incomer box, having door with locks, thickness of sheet CSRA 2 mm minimum, including 160 A MCCB 4P 50KA (Approved make : MK Honeywell / Legrand / Schneider) MCCB 160 A, 36KA, settable, LSIG complete with spreader, hardware, loading etc. complete RCBO 32/40A, DP, 30mA (Approved make : MK Honeywell / Legrand / Schneider)	2	NOS	1857.63	3715.26	INR Three Thousand Seven Hundred & Fifteen and Paise Twenty Six Only
9	Supply and fixing MCCB Incomer box, having door with locks, thickness of sheet CSRA 2 mm minimum, including 160 A MCCB 4P 50KA (Approved make : MK Honeywell / Legrand / Schneider) MCCB 160 A, 36KA, settable, LSIG complete with spreader, hardware, busbar etc as required.	3	NOS	29495.76	85487.28	INR Eighty Five Thousand Four Hundred & Eighty Seven and Paise Twenty Eight Only
10	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required. Above 35 sq. mm and upto 95 sq. mm	150	RMT	402.54	60381.00	INR Sixty Thousand Three Hundred & Eighty One Only
11	Supplying and fixing cable route marker with 10 cm X 10 cm X 5 mm Each thick G.I. plate with inscription there on, bolted /welded to 35 mm X 35 mm X 6 mm angle iron, 90 cm long and fixing the same in ground as required.	5	Nos	506.78	2533.90	INR Two Thousand Five Hundred & Thirty Three and Paise Ninety Only
12	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on cable tray as required. Above 95 sq. mm and upto 185 sq.mm	100	RMT	116.95	11695.00	INR Eleven Thousand Six Hundred & Ninety Five Only
13	END TERMINATION: Supply and installation of End termination of cables with PVC glands. Copper crimping type lugs should be used for copper cables and Cu lugs with soldering and ferrules for the following 1.kv class /Cu XLPE/PVC insulated using necessary crimping tool and all other accessories as required and including the cost of all materials, labour, Handling of Materials of equipment and machineries all lead lift, loading and unloading, transportation, if any other incidental charges at all level complete all as per specification and as directed by Engineer-in-charge. 1 Core x 70 Sqmm unarmoured flex copper Cable.	10	Each	169.49	1694.90	INR One Thousand Six Hundred & Ninety Four and Paise Ninety Only
14	END TERMINATION: Supply and installation of End termination of cables with PVC glands. Copper crimping type lugs should be used for copper cables and Cu lugs with soldering and ferrules for the following 1.kv class /Cu XLPE/PVC insulated using necessary crimping tool and all other accessories as required and including the cost of all materials, labour, Handling of Materials of equipment and machineries all lead lift, loading and unloading, transportation, if any other incidental charges at all level complete all as per specification and as directed by Engineer-in-charge. 1 Core x 120 Sqmm unarmoured flex copper Cable.	30	Each	254.24	7627.20	INR Seven Thousand Six Hundred & Twenty Seven and Paise Twenty Only
15	END TERMINATION: Supply and installation of End termination of cables with compression brass cable glands. Al crimping type lugs should be used for Al cables and Cu lugs with soldering and ferrules for the following 1.kv class Al/Cu XLPE/PVC insulated using necessary crimping tool and all other accessories as required and including the cost of all materials, labour, Handling of Materials of equipment and machineries all lead lift, loading and unloading, transportation, if any other incidental charges at all level complete all as per specification and as directed by Engineer-in-charge. 3.5 Core x 120 Sqmm (A2XFY) XLPE AL AR Cable. (Approved make : Dowells / C / Electrowerke)	4	Each	1132.20	4528.80	INR Four Thousand Five Hundred & Twenty Eight and Paise Eighty Only
16	Providing and fixing following rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, less=100% Cu and Operational Voltage 690V etc. as required. 160 A,36KA,FP/MCCB. Works includes modification in existing panel including bus link, terminations etc as complete.	1	Each	15569.49	15569.49	INR Fifteen Thousand Five Hundred & Sixty Nine and Paise Forty Nine Only
17	Supplying and fixing TP sheet steel enclosure on surface/ recess along with 16/25/32 A 415 V "C" curve TP MCB complete with connections, testing and commissioning etc. as required.	2	Nos	1446.61	2893.22	INR Two Thousand Eight Hundred & Ninety Three and Paise Twenty Two Only
18	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor: single core cable in surface/ recessed medium class PVC conduit as required. 2 X 4 sq. mm + 1 X 4 sq. mm earth wire (Approved make : Polycab / Finolex / RR Kabel)	200	RMT	316.10	63220.00	INR Sixty Three Thousand Two Hundred & Twenty Only
Total in Figures					2120006.58	INR Twenty One Lakh Twenty Thousand \$58 and Paise Fifty Eight Only

Quoted Rate in Figures		Select	0.00 NR Zero Only
Quoted Rate in Words			NR Zero Only