



भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान, पुणे
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH PUNE

(An Autonomous Institution, Ministry of Human Resource Development, Govt. of India)

IISER Pune Campus, Dr. Homi Bhabha Road, Pune-411 008.

Ph No 020 2590 8001 Fax 020 2588 7499 / 2589 8022

No: 54(2) /IISER/Pune/2020-21/

Dated 14/10/2019

NOTICE INVITING QUOTATION

Sealed quotations are hereby reinvited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to **3.00 PM on 22/10/2019** from eligible contractors registered with anyone CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite category for the work mentioned below. The quotations will be opened at 3.30 PM on the same day.

NAME OF WORK- Providing External Painting to Dining Hall & External Glass at IISER Pune.

Issue to –

Name and address of the agency –


Executive Engineer

Terms and Conditions:

- 1) The applicant should be eligible contractors registered with anyone CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite Category (any one) Applicant should submit attested or notarized copies of the valid Registration Certificate and Experience Certificate along with the quotation. Bidders not meeting the minimum eligibility criteria shall be summarily rejected.
- 2) Time period for completion of work shall be **15 (Fifteen) days** from the date of placing the work order by IISER Pune. The act of backing-out after opening of quotation will debar such agencies for participating in the future quotations of IISER PUNE. Bidder may e-mail queries on maintenance@iiserpune.ac.in or submit to IISER PUNE office in hard copy on all working days one day before submission date of quotation as specified above.
- 3) Notice Inviting Quotation (NIQ) document may be obtained from IISER PUNE at 121, Engineering Section , Main Building, IISER PUNE Campus, Dr.Homi Bhabha Road, Pashan, Pune-411008 between 10 AM to 4 PM on all working days before date of submission. Applicant may submit quotation by obtaining NIQ document from IISER PUNE website at <http://www.iiserpune.ac.in/links/tender-notices-and-eoi>

Sign & stamp of Agency-



NIQ : Page 1 of 5

- 4) All agencies need to submit their quotation in hard copy in sealed envelope containing by suitable means on and before **3 PM on 22/10/2019**. Quotation received after the date & time specified above shall not be accepted. Any delays , postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ . Rates quoted in words shall be treated as Final for deciding L1 bidder. The bid shall be submitted in the original bid document (as issued by the IISER, Pune or Webcopy) super scribing the name of work. Quoted rates shall be valid for 60 days from the date of opening of quotations. Rates shall be quoted in hand writing at the spaces provided in NIQ document. Commercial envelops of technically qualified bidders shall be opened accordingly . The offer of the agency should be commercially clear including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons.
- 5) Bids will be opened **on the same day at 3.30 PM** in the presence of agency or their authorized representatives, if any. Quotations submitted with any conditions shall be treated as conditional quotations and shall be summarily be rejected by IISER PUNE.
- 6) Quoted rates should be inclusive of cost of all the materials, labour cost , GST ,all taxes, royalties, cost of fuel, operator , octroi , duties , cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid separately. No, Bidder shall contact the IISER, Pune on any matter relating to his bid from the time of the bid opening to the time of issue of work order. Any effort by the Bidder to influence the IISER's bid evaluation, bid comparison or contract award decisions, may result in the rejection of his bid. Decision from competent authority/Engineer In-charge shall be final and binding to bidder in all the matters relating this work.
- 7) All approved makes shall be as specified in BOQ and as per CPWD specifications, agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work. The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location. Any scaffolding required shall be brought by contractor to complete the work with no cost to IISER Pune.

Sign & stamp of Agency-



No advance payment shall be made by IISER Pune. Quoted rates should be including GST , TDS and other applicable taxes . Income Tax and labour cess will be deducted from the bills of the work.

- 8) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER PUNE whenever specification CPWD/ IS specification are not available.
- 9) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws. All the safety measured shall be followed by the L1 agency as per prescribed norms during execution of work with all the necessary safety tools etc. Executing Agency shall sole techno-commercially responsible for the strict adherence of safety norms and allied compensations etc.
- 10) Agency should submit measurements and abstract sheets to IISER PUNE for the payments within 30 days from completion of work.


Executive Engineer

Encl : - Schedule of Quantity (BOQ) – As per Annexure A



ANNEX-A : Bill Of Quantity

Name of Work- Providing External Painting to Dining Hall & External Glass at IISER Pune.

Sr No	Description of Item	Unit	Qty.	Rate in words and Figures	Amount in words and Figure
1	Finishing walls with Acrylic Smooth exterior paint of required shade: Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing painted surface. All cracks shall be filled with similar colour all weather sealer from Sikha/Dr.Fixit/Fosroc. Quoted rate shall be including working at any height up to 20 Meter with all necessary safety harness, safety rope , guard ladder, cleaning of algae/fungus black spots etc complete. Rate including of all taxes, Material, labour, Scaffolding , GST nothing extra shall be payable.	Sqm	2500		
2	Providing & Fixing of laminated 12.50 mm sanditwched toughened glass bottom glass 5mm thickness+ top glass 6mm thickness. In between two glass 1.5 PVB. (Rate including filling silicon in joint & bottom rubber gasket self adhesive tape) accessories to be paid separately). Nothing extra shall be paid separately. Actual area of glass panel installed at site shall be measured for payments. Rate including safe removing of existing brocken glass panel and disposal within campus , including of all taxes, Material, labour, GST nothing extra shall be payable. Location Dining Block and Lecture Theatre complex	Sqm	35		
3	Lifting & Shifting Glass Panels by mechanical means by crane/ scaffolding or mechanical rope-pulley system up to 15 meter height including cost of hiring of machine/ crane, operator, fuel, shifting belt, Helper etc. Rate including of all taxes, Material, labour, GST nothing extra shall be payable. Payment of this item shall be associated with safe completion of Item No-2.	Job	1		



Sign & stamp of Agency-

4	<p>Providing and fixing double scaffolding system (cup lock type) on the exterior side of building/structure, upto 25 metre height, above ground level, including additional rows of scaffolding in stepped manner as per requirement of site, made with 40mm dia M.S. tube, placed 1.5 metre centre to centre, horizontal & vertical tubes joint with cup & lock system with M.S. Tubes, M.S. tube challis, M.S. clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for execution of work of cleaning and/ or pointing and/ or applying chemical and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connecting with the building etc, wherever required, if feasible, for inspection of work at required locations with essential safety features for the workmen etc., complete as per directions and approval of Engineer-in-charge. Note:- (1) The elevational area of the scaffolding shall be measured for payment purpose.(2) The payment will be made once only for execution of all items for such works. Rate including of all taxes, Material, labour, GST nothing extra shall be payable.</p>	Sqm	50	
TOTAL AMOUNT				




EXECUTIVE ENGINEER
IISER PUNE