



भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान, पुणे
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH PUNE

(An Autonomous Institution, Ministry of Human Resource Development, Govt. of India)
IISER Pune Campus, Dr. Homi Bhabha Road, Pune-411 008.
Ph No 020 2590 8001 Fax 020 2588 7499 / 2589 8022

No: 54(2) /IISER/Pune/2018-19/ 99

Dated 15/4/2019

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to **3.00 PM on 26/4/2019** from eligible contractors registered with CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite category for the work mentioned below. The quotations will be opened at 3.30 PM on the same day.

NAME OF WORK : PARTITION WORK FOR HSS FACULTY AND STUDENT SEATING SPACES AT GROUND FLOOR MAIN BUILDING AND ANTISTATIC FLOOR WORKS IN H CROSS AT IISER PUNE.

Issue to –

Name and address of the agency –


Executive Engineer

Terms and Conditions:

- 1) The applicant should be eligible contractors registered with CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite Category. Applicant should submit attested or notarized copies of the valid Registration Certificate/experience Certificate along with the quotation. Bidders not meeting the minimum eligibility criteria shall be summarily rejected.
- 2) Time period for completion of work shall be 1 (one) month from the date of placing the work order by IISER Pune. The act of backing-out after opening of quotation will debar such agencies for participating in the future quotations of IISER PUNE. Bidder may e-mail queries on maintenance@iiserpune.ac.in or submit to IISER Pune office in hard copy on all working days one day before submission date of quotation as specified above.
- 3) Notice Inviting Quotation (NIQ) document may be obtained from IISER Pune at 121, Engineering Section , Main Building, IISER PUNE Campus, Dr.Homi Bhabha Road, Pashan, Pune-411008 between 10 AM to 4 PM on all working days before date of submission. Applicant may submit quotation by obtaining NIQ document from IISER PUNE website at <http://www.iiserpune.ac.in/links/tender-notices-and-eoi>
- 4) All agencies need to submit their quotation in hard copy in sealed envelope containing technical qualification documents and experience certificates etc. and stamped , signed and quoted NIQ document to IISER PUNE office by suitable means on and before **3 PM on 26/4/2019**. Quotation received after the date & time specified above shall not be accepted. Any delays , postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ . Rates quoted in words shall be treated as Final for deciding L1 bidder. The bid shall be submitted in the original bid document (as issued by the IISER, Pune or Webcopy) super scribing the name of work. Quoted rates shall be valid for 60 days from the date of opening of quotations. Rates shall be quoted only in hand writing at the spaces provided in the NIQ document.

Sign & stamp of Agency-



NIQ : Page 1 of 7

Commercial envelopes of technically qualified bidders shall be opened accordingly . The offer of the agency should be commercially clear including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons.

- 5) Bids will be opened on the same day at 3.30 PM in the presence of agency or their authorized representatives, if any. Quotations submitted with any conditions shall be treated as conditional quotations and shall be summarily be rejected by IISER PUNE.
- 6) Quoted rates should be inclusive of cost of all the materials, labour cost , GST ,all taxes, royalties, cost of fuel, operator , octroi , duties , cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid separately. No, Bidder shall contact the IISER, Pune on any matter relating to his bid from the time of the bid opening to the time of issue of work order. Any effort by the Bidder to influence the IISER's bid evaluation, bid comparison or contract award decisions, may result in the rejection of his bid. Decision from competent authority/Engineer In-charge shall be final and binding to bidder in all the matters relating this work.
- 7) All approved makes shall be as specified in BOQ and as per CPWD specifications , agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work. The successful agency shall make his own arrangement for all Tools & tackles for work etc. complete in view of completion of work.
- 8) Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location. Any scaffolding required shall be brought by contractor to complete the work with no cost to IISER Pune.
No advance payment shall be made by IISER Pune. Quoted rates should be including GST , TDS and other applicable taxes . Income Tax and labour cess will be deducted from the bills of the work.
- 9) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER PUNE whenever specification CPWD/ IS specification are not available.
- 10) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws. All the safety measured shall be followed by the L1 agency as per prescribed norms during execution of work with all the necessary safety tools etc. Executing Agency shall sole techno-commercially responsible for the strict adherence of safety norms and allied compensations etc.
- 11) Agency should submit measurements and abstract sheets to IISER PUNE for the payments within 30 days from completion of work.

Akulkarni

Executive Engineer (E&M)

Encl : - Schedule of Quantity (BOQ) – As per Annexure A



Sign & stamp of Agency-

ANNEX-A : SCHEDULE OF QUANTITY (BOQ)

NAME OF WORK : PARTITION WORK FOR HSS FACULTY AND STUDENT SEATING SPACES AT GROUND FLOOR MAIN BUILDING AND ANTISTATIC FLOOR WORKS IN H CROSS AT IISER PUNE.

ITEM NO	DESCRIPTION	QUANTITY	UNIT	RATE in words and figures	AMOUNT
1	<p>Providing and fixing aluminum work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminum sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminum snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) .Powder coated aluminum (minimum thickness of powder coating 50 micron). Quoted rates shall be including GST , labour, lead , lift , transportation etc. complete. Nothing extra shall be paid separately. Approved Make JINDAL/BARUKA/Indian Aluminium Co.</p>				



Sign & stamp of Agency-

1.1	For fixed portion : Powder coated aluminum (minimum thickness of powder coating 50 micron).Quoted rates shall be including GST , labour, lead , lift , transportation etc. complete. Nothing extra shall be paid separately.	60.00	kg		
1.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots/Sliding and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminum (minimum thickness of powder coating 50 micron) Quoted rates shall be including GST , labour, lead , lift ; transportation etc. complete. Nothing extra shall be paid separately.	15.00	kg		
2	Providing and fixing double action hydraulic floor spring of approved brand and manufacture conforming to IS : 6315, having brand logo embossed on the body / plate with double spring mechanism and door weight up to 125 kg, for doors, including cost of cutting floors, embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of Engineer-in-charge. With stainless steel cover plate minimum 1.25 mm thickness. Quoted rates shall be including GST , labour, lead , lift , transportation etc. complete. Nothing extra shall be paid separately. Approved Makes Godrej/Dorma/Geze	1.00	each		



3	Providing and fixing 100mm brass locks (best make of approved quality) for aluminum doors including necessary cutting and making good etc. complete. Quoted rates shall be including GST , labour, lead , lift , transportation etc. complete. Nothing extra shall be paid separately. Approved Makes Godrej/Dorma/Hafle	1.00	each	
4	Providing and fixing Stainless Steel D handle of 300mm size etc. complete pair of in-out handle as per direction of Engineer-in-charge. Quoted rates shall be including GST , labour, lead , lift , transportation etc. complete. Nothing extra shall be paid separately. Approved Makes Godrej/Dorma/Hafle	1.00	pair	
5	Providing and fixing glazing in aluminum door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer-in-charge . Quoted rates shall be including GST , labour, lead , lift , transportation etc. complete. Nothing extra shall be paid separately. (Cost of aluminum snap beading shall be paid in basic item): With Toughen glass panes of 10 mm thickness	20.00	sqm	
6	Providing and fixing semi trasperant Frosted film to glass as per direction of Engineer Incharge. Film shade and pattern should be got approved from Engineer In-charge before taking-up works. Quoted rates shall be including GST , labour, lead , lift , transportation etc. complete. Nothing extra shall be paid separately. Approved Makes : 3M / Garware.	10.00	sqm	



7	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work. Quoted rate shall be including all taxes , duties , GST, etc. complete. Nothing extra shall be paid separately.	75.00	sqm	
8	Removal and re-fixing of modular false ceiling of size 595X595 along with grid system as directed by Engineer in charge. Rate shall be inclusive of scaffolding etc. complete . Nothing extra shall be paid separately.	10.00	sqm	
	LAB No-222 , H cross			
9	Antistatic Vinyl flooring - 2mm thick : Providing and laying of Antistatic Vinyl Sheet Flooring manufactured by Armstrong - Pastel SD Antistatic Vinyl flooring (Thickness 2.0mm) (Sheet- Length 16-25mtrs x width 1.8mtrs) / Tarket Antistatic vinyl flooring Eclipse SD / TORO SD (Sheet- Length 23mtrs x width 02mtrs) / Antistatic vinyl flooring GERFLOR-MIPOLAM Elegance EL5 (Sheet- Length 23mtrs x width 02mtrs) / With accessories- Cove Fillet and Weld cord. All joints between vinyl sheets shall be sealed & welded using approved colour welding rod to match the flooring colour after 24 hours of laying of rolls. Welding and seaming shall be done using automatic hot seam welding machine. Rate to include protection with 500 micron LDPE sheet with taped edges until completion of all other activities as the floor as per the instructions of Engineer in charge. Vinyl sheets should be laid over the existing vitrified flooring 2 to 3 mm thick. Flooring shall be laid 200mm on adjoin wall and copper strips of 0.5mm thick & 20mm wide shall provided to form the grid of 1000mm X 1000mm & to be properly connected with nearest earthing terminal . Vinyl sheets shall be manufactured as per CE norms and EN 649/EN ISO10851. Antistatic parameters shall be as per EN 61340 / EN 1815 / EN 1081. Actual area of flooring	30.00	sqm	



laid at site shall be measured for payments. Rate shall be including all taxes, duties, wastage, capping accessories, material testing samples and testing expenses etc. complete. Nothing extra paid separately. Approved make **Armstrong / Tarket / GERFLOR**

Total



(Signature)

**Executive Engineer
IISER Pune**

