



भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान, पुणे
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH PUNE

(An Autonomous Institution, Ministry of Human Resource Development, Govt. of India)

IISER Pune Campus, Dr. Homi Bhabha Road, Pune-411 008.

Ph No 020 2590 8001 Fax 020 2588 7499 / 2589 8022

No: 54(2) /IISER/Pune/2019-20/183

Dated 05/07/2019

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to 3.00 PM on 12/07/2019 from approved and eligible contractors registered with CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite category or Water Tank Cleaning expert agencies for the work mentioned below. The quotations will be opened at 3.30 PM on the same day.

NAME OF WORK- PROVIDING ALUMINUM PARTITION & DOOR TO LAB 214 , REMOVING AND RELAYING OF GI PIPELINE AT IISER PUNE.

Issue to –

Name and address of the agency –



EXECUTIVE ENGINEER

Terms and Conditions:

- 1) The applicant should be approved and eligible contractors registered with CPWD, Maharashtra State PWD, Railways, MES in appropriate category (any one) of Civil/Composite Category or Water Tank Cleaning expert agencies with similar experience of cleaning cycle at one client department . Applicant should submit attested or notarized copies of the Valid Registration Certificate or Experience Certificate along with the quotation. Bidders not meeting the minimum eligibility criteria shall be summarily rejected.
- 2) Time period for completion of work shall be 15 (Fifteen) days from the date of placing the work order by IISER Pune. The act of backing-out after opening of quotation will debar such agencies for participating in the future quotations of IISER PUNE. Bidder may e-mail queries on maintenance@iiserpune.ac.in or submit to IISER PUNE office in hard copy on all working days one day before submission date of quotation as specified above.
- 3) Notice Inviting Quotation (NIQ) document may be obtained from IISER PUNE at 121, Engineering Section , Main Building, IISER PUNE Campus, Dr.Homi Bhabha Road, Pashan, Pune-411008 between 10 AM to 4 PM on all working days before date of submission. Applicant may submit quotation by obtaining NIQ document from IISER PUNE website at <http://www.iiserpune.ac.in/links/tender-notices-and-eoi>
- 4) All agencies need to submit their quotation in hard copy in a sealed envelope containing containing qualification documents and experience certificates etc and stamped , signed and quoted NIQ document to IISER PUNE office by suitable means on and before 3 PM on 12/7/2019. Quotation received after the date & time specified above shall not be accepted. Any delays , postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ . Rates quoted in words shall be treated as Final for deciding L1 bidder. The bid shall be submitted in the original bid document (as issued by the IISER, Pune or Webcopy) super scribing the name of work. Quoted rates shall be valid for 60 days from the date of opening of quotations. Rates shall be quoted in hand writing at the spaces provided in NIQ document. Commercial

envelops of technically qualified bidders shall be opened accordingly with intimation to technically qualified bidders. The offer of the agency should be commercially clear including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons.

- 5) Bid/Bids will be opened on the same day at 3.30 PM in the presence of agency or their authorized representatives, if any. Quotations submitted with any conditions shall be treated as conditional quotations and shall be summarily be rejected by IISER PUNE.
- 6) Quoted rates should be inclusive of cost of all the materials, labour cost , GST ,all taxes, octroi , duties , cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid separately. No, Bidder shall contact the IISER, Pune on any matter relating to his bid from the time of the bid opening to the time of issue of work order. Any effort by the Bidder to influence the IISER's bid evaluation, bid comparison or contract award decisions, may result in the rejection of his bid.
- 7) All approved makes shall be as specified in BOQ and as per CPWD specifications , agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work. The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location. Any scaffolding required shall be brought by contractor to complete the work with no cost to IISER Pune.
No advance payment shall be made by IISER Pune. Quoted rates should be including GST , TDS and other applicable taxes . Income Tax and labour cess will be deducted from the bills of the work.
- 8) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER PUNE whenever specification CPWD/ IS specification are not available.
- 9) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws. All the safety measured shall be followed by the L1 agency as per prescribed norms during execution of work with all the necessary safety tools etc. Executing Agency shall sole techno-commercially responsible for the strict adherence of safety norms and allied compensations etc.
- 10) Agency shall submit measurements and abstract sheets to IISER PUNE for the payments within 30 days from completion of work.
- 11) Agency shall maintain and submit a copy of workman compensation policy, ESIC, PF and insurance of deployed labour before starting of work.


EXECUTIVE ENGINEER

Encl : - Schedule of Quantity (BOQ) – As per Annexure A



ANNEX-A

NAME OF WORK- PROVIDING ALUMINIUM PARTITION & DOOR TO LAB 214 , REMOVING AND RELAYING OF GI PIPELINE AT IISER PUNE.

| Sr. | Description | Unit | Qty. | Rate | Amount |
|-----|---|------|------|------|--------|
| 1 | Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, panelling and dash fasteners to be paid for separately) : Quoted rates shall be including GST. | | | | |
| 1.1 | Powder coated aluminium (minimum thickness of powder coating 50 micron) | Kg | 90 | | |
| 1.2 | For shutters of doors, windows & ventilators including providing and fixing hinges/pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately). Quoted rates shall be including GST. | kg | 30 | | |
| 2 | Providing and fixing double action hydraulic floor spring of approved brand and manufacture conforming to IS : 6315, having brand logo embossed on the body / plate with double spring mechanism and door weight upto 125 kg, for doors, including cost of cutting floors, embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per | sqm | 4 | | |



| | | | | | |
|---|---|------|----|--|--|
| | the direction of Engineer-in-charge. With stainless steel cover plate minimum 1.25 mm thickness. Quoted rates shall be including GST. | | | | |
| 3 | Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5.50 mm thickness. Quoted rates shall be including GST. | sqm | 18 | | |
| 4 | Providing and fixing 12 mm thick pre-laminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer-in-charge. - Pre-laminated particle board with decorative lamination on both sides. Quoted rates shall be including GST. | sqm | 9 | | |
| 5 | Providing and fixing aluminium round shape handle of outer dia 100 mm with SS screws etc. complete as per direction of Engineer-in-charge Powder coated minimum thickness 50 micron aluminium. Quoted rates shall be including GST. | Each | 4 | | |
| 6 | Providing and fixing 100mm brass locks (best make of approved quality) for aluminium doors including necessary cutting and making good etc. complete. Quoted rates shall be including GST. | Each | 2 | | |



| Removal and re-laying of GI pipeline | | | | | |
|---|--|-------|-----|--|--|
| 7 | Excavation , removing of GI pipers , filling , transportation from NCL campus to IISER Pune Campus , laying of line as per direction of Engineer In charge below 150mm below soil . Quoted rate shall be including cost of dismantling of pipes from NCL campus on ground or below ground , removing from Couper , cost of Teflon tape, habak, shifting to IISER Pune Campus , laying as per approved layout , site threading where ever required etc complete. Nothing extra shall be paid separately. Cost of fittings shall be paid separately during installation , quoted rate shall be including GST. For 63mm or lower dia GI pipe. | meter | 500 | | |
| 8 | Supply of GI fittings 63mm GI Pipe Coupler, Quoted rates shall be including GST. | Each | 25 | | |
| 9 | Supply of GI fittings 63mm GI Pipe unequal Tee 63-25-63mm , Quoted rates shall be including GST. | Each | 25 | | |
| 10 | Supply of GI fittings 25mm GI Pipe Coupler with 450mm long barrel piece and end cap., Quoted rates shall be including GST. | Each | 25 | | |
| Total Amount | | | | | |

Akshay Kamli
EXECUTIVE ENGINEER

