



भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान, पुणे
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH PUNE
(An Autonomous Institution, Ministry of Human Resource Development, Govt. of India)

IISER Pune Campus, Dr. Homi Bhabha Road, Pune-411 008.
Ph No 020 2590 8001 Fax 020 2588 7499 / 2589 8022

No: 54(2) /IISER/Pune/2019-1/ 283

Dated 30/10/2019

NOTICE INVITING QUOTATION

Sealed quotations are hereby **Reinvited** by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to **3.00 PM on 06/11/2019** from eligible contractors registered with **Anyone** CPWD, Maharashtra State PWD, Railways, and MES in appropriate category of Civil/Composite category for the work mentioned below. The quotations will be opened at 3.30 PM on the same day.

NAME OF WORK- Providing Shot Put & Discus throws Platform, oil painting, Sea sand at IISER Pune.

Issue to –

Name and address of the agency –


Executive Engineer

Terms and Conditions:

- 1) The applicant should be eligible contractors registered with **Anyone** CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite Category. Applicant should submit attested or notarized copies of the valid Registration Certificate and Experience Certificate along with the quotation. Bidders not meeting the minimum eligibility criteria shall be summarily rejected.
- 2) Time period for completion of work shall be **15 (Fifteen) days** from the date of placing the work order by IISER Pune. The act of backing-out after opening of quotation will debar such agencies for participating in the future quotations of IISER PUNE. Bidder may e-mail queries on maintenance@iiserpune.ac.in or submit to IISER PUNE office in hard copy on all working days one day before submission date of quotation as specified above.
- 3) Notice Inviting Quotation (NIQ) document may be obtained from IISER PUNE at 121, Engineering Section , Main Building, IISER PUNE Campus, Dr.Homi Bhabha Road, Pashan, Pune-411008 between 10 AM to 4 PM on all working days before date of submission. Applicant may submit quotation by obtaining NIQ document from IISER PUNE website at <http://www.iiserpune.ac.in/links/tender-notices-and-eoi>

Sign & stamp of Agency-



NIQ : Page 1 of 5

- 4) All agencies need to submit their quotation in hard copy in sealed envelope containing by suitable means on and before **3 PM on 06/11/2019**. Quotation received after the date & time specified above shall not be accepted. Any delays , postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ . Rates quoted in words shall be treated as Final for deciding L1 bidder. The bid shall be submitted in the original bid document (as issued by the IISER, Pune or Web copy) super scribing the name of work. Quoted rates shall be valid for 60 days from the date of opening of quotations. Rates shall be quoted in hand writing at the spaces provided in NIQ document. Commercial envelops of technically qualified bidders shall be opened accordingly . The offer of the agency should be commercially clear including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons.
- 5) Bids will be opened **on the same day at 3.30 PM** in the presence of agency or their authorized representatives, if any. Quotations submitted with any conditions shall be treated as conditional quotations and shall be summarily be rejected by IISER PUNE.
- 6) Quoted rates should be inclusive of cost of all the materials, labour cost , GST ,all taxes, royalties, cost of fuel, operator , octroi , duties , cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid separately. No, Bidder shall contact the IISER, Pune on any matter relating to his bid from the time of the bid opening to the time of issue of work order. Any effort by the Bidder to influence the IISER's bid evaluation, bid comparison or contract award decisions, may result in the rejection of his bid. Decision from competent authority/Engineer In-charge shall be final and binding to bidder in all the matters relating this work.
- 7) All approved makes shall be as specified in BOQ and as per CPWD specifications, agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work. The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location. Any scaffolding required shall be brought by contractor to complete the work with no cost to IISER Pune. No advance payment shall be made by IISER Pune. Quoted rates should be including GST , TDS and other applicable taxes . Income Tax and labour cess will be deducted from the bills of the work.

Sign & stamp of Agency-



ANNEX-A : Bill Of Quantity

Name of Work- Providing Shot Put & Discus throw Platform, oil painting, Sea sand at IISER Pune.

Sr No	Description of Item	Unit	Qty.	Rate in words and Figures	Amount in words and Figure
1	Construction of Shot Put & discus throw circle platform of diameter 2200 mm and 2500mm respectively as per standard drawings/designs. Work including cleaning of ground, levelling of existing soil, excavation of soil up to soft murrum, compaction of excavated surface by compactor with watering, Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : laying of concrete 1:3:6 (1 Cement : 3 coarse sand (zone-II): 6 graded stone aggregate 40 mm nominal size) 100mm thick Also providing of 100mm height peripheral MS flat 3mm thick to shot put & discus throw circle & 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size) 100mm thick & top smooth finish finished with a floating coat of neat cement. Curing to 07 days with watering & filling soil, marking by road marking paint etc complete. (Rate including of all taxes duties GST, Wastage nothing extra shall be payable)	Each	2		
2	Modification & Repairing of Existing basketball Pole with required Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per direction of Sports Incharge. Steel work carried out as per drawing.(Rate including of all taxes duties GST, Wastage nothing extra shall be payable)	Job	1		



- 8) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER PUNE whenever specification CPWD/ IS specification are not available.
- 9) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws. All the safety measures shall be followed by the L1 agency as per prescribed norms during execution of work with all the necessary safety tools etc. Executing Agency shall be solely techno-commercially responsible for the strict adherence of safety norms and allied compensations etc.
- 10) Agency should submit measurements and abstract sheets to IISER PUNE for the payments within 30 days from completion of work.


Executive Engineer

Encl : - Schedule of Quantity (BOQ) – As per Annexure A



3	Painting with synthetic enamel paint, having VOC (Volatile Organic Compound) content less than 150 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.(Rate including of all taxes duties GST, Wastage nothing extra shall be payable)	Sqm	50	
4	Removing & Shifting of existing sand from pit & Supplying and filling screened white fine sea sand from approved source & quality (sample to be approved from Engineer-in - Charge) filling in play area pits, consolidation, top dressing in line and level, carriage, loading and unloading, wastage, royalty, all taxes etc. complete as per the direction of Engineer in charge. Net quantity of filled sand at site shall be measured in cubic meters for payment. (Rate including of all taxes duties GST, Wastage nothing extra shall be payable)	Cum	22	
				TOTAL AMOUNT

N. Kulkarni

EXECUTIVE ENGINEER

IISER PUNE



Sign & stamp of Agency-

NIQ : Page 5 of 5

