



भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान पुणे

(मानव संसाधन विकास मंत्रालय, भारत सरकार का स्वायत्त संस्थान)

डॉ. होमी भाभा मार्ग, पुणे : 411 008

INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH PUNE

(An Autonomous Institution, Ministry of Human Resource Development, Govt. of India)

IISER Pune Campus, Dr. Homi Bhaba Road, Pune

No: 54(2) /IISER/Pune/2020-21/ 56

Dated : 23.2.2021

NOTICE INVITING QUOTATION

Sealed spot quotations are hereby invited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to **3.00 PM on 15.3.2021** from approved and eligible contractors registered with CPWD, Maharashtra State PWD, Railways, MES in appropriate category for Civil/ (B&C) works for the work mentioned below. The quotations will be opened at 3.30 PM on the same day.

NAME OF WORK : PROVIDING AND FIXING CHAIN LINK FENCING AND GATE TO CHILDREN PARK AT IISER PUNE

Issue to –

Name and address of the agency –


Executive Engineer,

Terms and Conditions:

- 1) The applicant should be registered with CPWD in western region, Maharashtra State PWD, MES, Railways in appropriate category for Civil/ (B & C) works. The registration certificate should be valid till the last date of receipt of tender. Applicant should submit attested or notarized copies of the valid registration certificate along with quotation.
- 2) Time period for completion of work shall be 15 (Fifteen) days from the date of placing the work order by IISER Pune. The act of backing-out after quotation will debar such agencies for participating in future quotations of IISER PUNE. Bidder may e-mail queries on maintenance@iiserpune.ac.in or submit to IISER PUNE office in hard copy on all working days before a day of submission date of quotation.
- 3) Quotation can be obtained from IISER PUNE Engineering office at Main Building between 10 AM to 4 PM on all working days before date of submission. Applicant may quote by downloading quotation document from IISER PUNE website.
- 4) All agencies need to submit their quotation in hard copy in a sealed envelope to this office by suitable means on and before **3 PM on 15.3.2021** Quotation received after the date & time specified above shall not be accepted. Any delays , postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ . The bid shall be submitted in the original bid document (as issued by the IISER, Pune) super scribing the name of work. Rates quoted in the words shall be treated as final for deciding L1 bidder.

Sign and Seal of Agency

Page 1 of 4



21-22/09 (1611)

- 5) Quotations will be opened on the **same day at 3.30 PM** in the presence of agency or their authorized representatives, if any. The offer of the agency should be commercially clear including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons.
- 6) Quotations submitted with any conditions shall be treated as 'Conditional Quotation' and shall be summarily be rejected by IISER PUNE.
- 7) Quoted rates should be inclusive of cost of all the materials, labour cost , GST , all taxes, octroi , duties , cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid separately.
- 8) All approved makes shall be as specified in BOQ and as per CPWD specifications , agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work.
The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location.
No advance payment shall be made by IISER Pune. Quoted rates should be including GST, TDS and other applicable taxes and cess will be deducted from the bills of the work as applicable.
- 9) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER PUNE whenever specification CPWD/ IS specification are not available.
- 10) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws.
- 11) L1 Agency to submit actual measurements and abstract sheet to IISER PUNE within 30 days from completion of work.


Executive Engineer,
IISER Pune

Encl: - Schedule of Quantity (BOQ) – As per Annexure



ANNEX-A – ESTIMATE

NAME OF WORK : PROVIDING AND FIXING CHAIN LINK FENCING AND GATE TO CHILDREN PARK AT IISER PUNE

BILL OF QUANTITY

ITEM NO	DESCRIPTION	QUANTITY	UNIT	RATE IN WORD AND FIGURES	AMOUNT
1	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position including welding and bolted with special shaped washers etc. complete Actual steel work fixed at site with dash screw fasteners shall be measured for payments. Quoted rate shall be including labour, material, lead, lift, transportation, taxes, duties etc complete. Nothing extra shall be paid separately. Mild steel shall be issued departmentally by IISER Pune. Quoted rate shall be cost of lead of steel from any location of campus to site, removing structural members from random scrap stack, removing of stacked steel or wooden scrap from selected members as approved Engineer In Charge. Actual weight of steel work at site shall be measured for payments.	500.00	kg		
2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. For Angles of Chain Link Fencing	500.00	kg		
3	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	200.00	Kg		
4	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. Made of G.I. wire of dia. 4	200.00	SQM		



	mm, PVC coated to achieve outer dia not less than 5 mm in required colour and shade.				
5	Fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. Made of G.I. wire of dia. 4 mm, PVC coated to achieve outer dia not less than 5 mm in required colour and shade.	100.00	SQM		
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand (zone-II) : 4 graded stone aggregate 40 mm nominal size). Quoted rate shall be including labour, material, lead, lift, transportation, taxes, duties etc complete. Nothing extra shall be paid separately.	5.00	Cum		
7	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	6.00	Cum		
8	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work. Actual area painted shall be measured for payments. Quoted rate shall be including labour, material, lead, lift, transportation, taxes, duties etc complete. Nothing extra shall be paid separately. Approved Makes : Indigo / Asian / Nerolac	100.00	sqm		
					Total



Skulkarni
Executive Engineer