



भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान, पुणे
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH PUNE

(An Autonomous Institution, Ministry of Human Resource Development, Govt. of India)

IISER Pune Campus, Dr. Homi Bhabha Road, Pune-411 008.

Ph No 020 2590 8001 Fax 020 2588 7499 / 2589 8022

No: 54(2)IISER/Pune/2019-20/ 98

Dated 12/04/2019

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to 3.00 PM on 22/04/2019 from eligible contractors registered with CPWD, Maharashtra State PWD, Railways, MES in appropriate category for Civil /Composite or agencies with suitable experience for work mentioned below. The quotation will be opened at 3.30 PM on the same day.

NAME OF WORK : AUGMENTATION AND CLEANING OF WELL AT IISER PUNE.

Issue to –

Name and address of the agency –

A. Kulkarni

EXECUTIVE ENGINEER

IISER PUNE

Terms and Conditions:

- 1) The applicant should be eligible contractors registered with CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite category or agency/agencies with suitable experience. Applicant should be submitting attested or notarized copies of the valid Registration certificate and experience certificate with the quotation. Bidders not meeting the minimum eligibility criteria shall be summarily rejected.
- 2) Time period for completion of work shall be 30 (Thirty) days from the date of placing the work order by IISER Pune. The act of backing-out after opening of quotation will debar such agencies for participating in the future quotations of IISER PUNE. Bidder may e-mail queries on maintenance@iiserpune.ac.in or submit to IISER PUNE office in hard copy on all working days one day before submission date of quotation as specified above.
- 3) Notice Inviting Quotation (NIQ) document may be obtained from IISER PUNE at 121, Engineering Section , Main Building, IISER PUNE Campus, Dr.Homi Bhabha Road, Pashan, Pune-411008 between 10 AM to 4 PM on all working days before date of submission.



Applicant may submit quotation by obtaining NIQ document from IISER PUNE website at <http://www.iiserpune.ac.in/links/tender-notices-and-eoi>

- 4) All agencies need to submit their quotation in hard copy in sealed envelope containing qualification documents and experience certificates etc and stamped, signed and quoted NIQ document to IISER PUNE office by suitable means on and before 3 PM on 22/4/2018. Quotation received after the date & time specified above shall not be accepted. Any delays , postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ . Rates quoted in words shall be treated as Final for deciding L1 bidder. The bid shall be submitted in the original bid document (as issued by the IISER, Pune or Webcopy) super scribing the name of work. Quoted rates shall be valid for 60 days from the date of opening of quotations. Rates shall be quoted by hand writing at the spaces provided in NIQ document.
- 5) Quotations will be opened on the same day at 3.30 PM in the presence of agency or their authorized representatives, if any. The offer of the agency should be commercially clear including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons.
- 6) Quotations submitted with any conditions shall be treated as conditional quotations and shall be summarily be rejected by IISER PUNE.
- 7) Quoted rates should be inclusive of cost of all the materials, labour cost , GST ,all taxes, octroi , duties , cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid separately. No, Bidder shall contact the IISER, Pune on any matter relating to his bid from the time of the bid opening to the time of issue of work order. Any effort by the Bidder to influence the IISER's bid evaluation, bid comparison or contract award decisions, may result in the rejection of his bid.
- 8) All approved makes shall be as specified in BOQ and as per CPWD specifications , agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work. The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location.



No advance payment shall be made by IISER Pune. Quoted rates should be including GST , TDS and other applicable taxes . Income Tax and labour cess will be deducted from the bills of the work.

- 9) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER PUNE whenever specification CPWD/ IS specification are not available.
- 10) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws. All the safety measures shall be followed by the L1 agency as per prescribed norms during execution of work with all the necessary safety tools etc. Executing Agency shall be sole techno-commercially responsible for the strict adherence of safety norms and allied compensations etc.
- 11) Agency should submit measurements and abstract sheets to IISER PUNE for the payments within 30 days from completion of work.



EXECUTIVE ENGINEER

IISER PUNE

Encl : - Schedule of Quantity (BOQ) – As per Annexure A

Sign & stamp of Agency-



ANNEX-A : SCHEDULE OF QUANTITY (BOQ)

NAME OF WORK : AUGMENTATION AND CLEANING OF WELL AT IISER PUNE.

ITEM NO	DESCRIPTION	Unit	Quantity	Rate in words and figures	Amount
1	Clearing jungle including uprooting of rank vegetation, grass, brush wood on ground level and removal of rubbish outside the periphery of well of the area cleared. (Quoted rates shall be including GST, Transportation, Lead, Lift, Insurance, Scaffolding, Safety Tools, etc. Nothing extra shall be payable). Collected debris/rubbish shall be deposited in location as approved by Engineer In-charge. Nothing extra shall be paid separately.	Job	1		
2	Hiring of electrical pump 5.0 hp for dewatering purpose including charges of pump operator, diesel, oil etc. On per days basis with suction pipe & other access. Complete as per direction of engineer-in-charge. (Quoted rates shall be including GST, Transportation, Lead, Lift, Insurance, Scaffolding, Safety Tools, etc. Nothing extra shall be payable)	Day	15		
3	Cleaning of well by removing debris , mud , silt , vegetation , floating material and submerged rubbish etc complete other than water from the bottom of well by mechanical lift/crane including all leads & lift, disposal of removed material from well with in campus as approved by Engineer In-charge . Quoted rate shall including cost towards with deployment of labour, crane operator, supervisor, diesel, oil etc. complete. Suitable manpower shall be deployed for cleaning operation at well bottom with all approved safety harness during work inside the well , for collecting of mud, loose soil, stones, etc & filling into crane bucket & four labours	Day	15		



	shall be deployed for unloading of bucket. Any other method other than specified shall be intimated accordingly. Rate including of all operations. (Quoted rates shall be including GST, Transportation, Lead, Lift, Insurance, Scaffolding, Safety Tools, etc. Nothing extra shall be payable)				
4	Drilling of horizontal Boring/drilling bore well of 75mm dia in open well at bottom, by suitable method, including drilling in all strata, including hire & running charges of all equipment's, tools, plants & machineries required for the job, all complete as per direction of Engineer -in-charge. Quoted rates shall be including GST, Transportation, Lead, Lift, Insurance, Scaffolding, Safety Tools, etc. Nothing extra shall be payable)	Mtr.	200		
5	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within campus lead as per direction of Engineer-in-charge. In mud mortar. Quoted rates shall be including GST, Transportation, Lead, Lift, Insurance, Scaffolding, Safety Tools, etc. Nothing extra shall be payable)	Cum	5		
6	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 sand) . (Quoted rates shall be including GST, Transportation, Lead, Lift, Insurance, Scaffolding, Safety Tools, etc. Nothing extra shall be payable)	Cum	5		
7	12 mm cement plaster of mix : 1:4 (1 cement: 4 sand) . Quoted rates shall be including GST, Transportation, Lead, Lift, Insurance, Scaffolding, Safety Tools, etc. Nothing extra shall be payable)	Sqm	20		



8	<p>Removing & refixing of existing Chain link with MS angle , including refixing of ms angle with Cement 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) pedestal size 200x200x200 @ 3.0 mtr center. Strengthening chain link with 2mm dia wire or nuts/ bolts and washers etc as required complete as per the direction of Engineer-in-charge. (Quoted rates shall be including GST, Transportation, Lead, Lift, Insurance, Scaffolding, Safety Tools, etc. Nothing extra shall be payable)</p>	Job	1		
TOTAL AMOUNT					

Agency Name-

Date-

M. Kulkarni

**EXECUTIVE ENGINEER
IISER PUNE**

