



भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान, पुणे
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH PUNE

(An Autonomous Institution, Ministry of Human Resource Development, Govt. of India)

IISER Pune Campus, Dr. Homi Bhabha Road, Pune-411 008.

Ph No 020 2590 8001 Fax 020 2588 7499 / 2589 8022

No: 54(2) /IISER/Pune/2017-18/ 194

Dated 28/11/2018

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to **3.00 PM on 11/12/2018** from eligible contractors registered with CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite category with suitable experience for the work mentioned below. The quotations will be opened at 3.30 PM on the same day.

NAME OF WORK- PROVIDING CALCIUM SILICATE CEILING AT LAB NO-215 , H CROSS AND PARTITION WORK AT SOUVENIR AT IISER PUNE.

Issue to –

Name and address of the agency –


Executive Engineer

Terms and Conditions:

- 1) The applicant should be eligible contractors registered with CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite Category OR agency/ agencies with suitable experience. Applicant should submit attested or notarized copies of the valid Registration Certificate and Experience Certificate along with the quotation. Bidders not meeting the minimum eligibility criteria shall be summarily rejected.
- 2) Time period for completion of work shall be **15 (Fifteen) days** from the date of placing the work order by IISER Pune. The act of backing-out after opening of quotation will debar such agencies for participating in the future quotations of IISER PUNE. Bidder may e-mail queries on maintenance@iiserpune.ac.in or submit to IISER PUNE office in hard copy on all working days one day before submission date of quotation as specified above.
- 3) Notice Inviting Quotation (NIQ) document may be obtained from IISER PUNE at 121, Engineering Section , Main Building, IISER PUNE Campus, Dr.Homi Bhabha Road, Pashan, Pune-411008 between 10 AM to 4 PM on all working days before date of submission. Applicant may submit quotation by obtaining NIQ document from IISER PUNE website at <http://www.iiserpune.ac.in/links/tender-notices-and-eoi>
- 4) All agencies need to submit their quotation in hard copy in sealed envelope containing by suitable means on and before **3 PM on 11/12/2018**. Quotation received after the date & time specified above shall not be accepted. Any delays , postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ . Rates quoted in words shall be treated as Final for deciding L1 bidder. The bid shall be submitted in the original bid document (as issued by the IISER, Pune or Webcopy) super scribing the name of work. Quoted rates shall be valid for 60 days from the date of opening of quotations. Rates shall be quoted in hand writing at the spaces provided in NIQ document. Commercial envelopes of technically qualified bidders shall be opened accordingly . The offer of the agency should be commercially clear

Sign & stamp of Agency-

NIQ : Page 1 of 5



including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons.

- 5) Bids will be opened **on the same day at 3.30 PM** in the presence of agency or their authorized representatives, if any. Quotations submitted with any conditions shall be treated as conditional quotations and shall be summarily be rejected by IISER PUNE.
- 6) Quoted rates should be inclusive of cost of all the materials, labour cost , GST ,all taxes, royalties, cost of fuel, operator , octroi , duties , cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid separately. No, Bidder shall contact the IISER, Pune on any matter relating to his bid from the time of the bid opening to the time of issue of work order. Any effort by the Bidder to influence the IISER's bid evaluation, bid comparison or contract award decisions, may result in the rejection of his bid. Decision from competent authority/Engineer In-charge shall be final and binding to bidder in all the matters relating this work.
- 7) All approved makes shall be as specified in BOQ and as per CPWD specifications , agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work. The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location. Any scaffolding required shall be brought by contractor to complete the work with no cost to IISER Pune.
No advance payment shall be made by IISER Pune. Quoted rates should be including GST , TDS and other applicable taxes . Income Tax and labour cess will be deducted from the bills of the work.
- 8) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER PUNE whenever specification CPWD/ IS specification are not available.
- 9) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws. All the safety measured shall be followed by the L1 agency as per prescribed norms during execution of work with all the necessary safety tools etc. Executing Agency shall sole techno-commercially responsible for the strict adherence of safety norms and allied compensations etc.
- 10) Agency should submit measurements and abstract sheets to IISER PUNE for the payments within 30 days from completion of work.



Executive Engineer

Encl : - Schedule of Quantity (BOQ) – As per Annexure A



Sign & stamp of Agency-

NIQ : Page 2 of 5

Name of Work- Providing Calcium Silicate Ceiling at Lab No-215 , H Cross at IISER Pune

Sr No	Description of Item	Unit	Qty.	Rate in words and Figures	Amount in words and Figure
1	Removal of modular false ceiling of size 595X595 along with grid system and stacking grid and tiles polypacks in suitable boxes at location in IISER PUNE campus as directed by Engineer in charge. Rate shall be inclusive of GST , scaffolding , polypacks , cartoon boxes etc. complete . Nothing extra shall be paid separately.	100.00	Sqm		
2	Providing & fixing false ceiling at all height including providing & fixing of framework made of special section, power pressed from M.S. sheets and galvanised with zinc coating of 120 gms/ sqm (both side inclusive) as per IS : 277 and consisting of angle cleat of size 25mm wide x 1.6mm thick with flanges of 27mm and 37mm, at 1200mm c/c, one flange fixed to the ceiling with dash fastener 12.5mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25 x10 x0.50mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I channels 45 x15 x 0.90mm running at the spacing of 1200 mm c/c, to which the ceiling section 0.5mm thick bottom wedge of 80mm with tapered flanges of 26 mm each having lips of 10.5mm, at 450mm c/c, shall be fixed in a direction perpendicular to G.I intermediate channel with connecting clip made out of 2.64mm dia x 230mm long G.I wire at every junction, including fixing perimeter channels 0.50mm thick 27mm high having flanges of 20mm and 30mm long, the perimeter of ceiling fixed to wall/ partitions with the help of Rawl plugs at 450mm centre, with 25mm long dry wall screws @ 230mm interval, including fixing of Calcium Silicate Board to ceiling section and perimeter channels with the help of dry wall screws of size 3.5 x25mm at 230mm c/c, including jointing & finishing to a flush finish of tapered and square edges of the board with recommended jointing compounds, jointing tapes, finishing with jointing compounds in three layers covering up to 150mm on both sides of joints and two coats of primer suitable for boards, all as per manufacture's specification and also including the cost of making opening for light fittings, grills, diffusers, cut outs made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the	100.00	Sqm		



	Calcium Silicate Board made with Calcareous & Siliceous materials reinforced with cellulose fiber manufactured through autoclaving process. Quoted rates shall be including GST , labour, lead , lift , transportation etc complete. Nothing extra shall be paid separately.			
3	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade :Two or more coats on new work. Approved Make Asian/Burger/Nerolac. Quoted rates shall be including GST , labour, lead , lift , transportation etc complete. Nothing extra shall be paid separately.	100	Sqm	
TOTAL				

Name of Work- Providing partition at Souvenir Shop at Dining Hall at IISER Pune

4	<p>Providing and fixing partition upto ceiling height consisting of G.I. frame and required board, including providing and fixing of frame work made of special section power pressed/ roll form G.I. sheet with zinc coating of 120 gms/sqm(both side inclusive), consisting of floor and ceiling channel 50mm wide having equal flanges of 32 mm and 0.50 mm thick, fixed to the floor and ceiling at the spacing of 610 mm centre to centre with dash fastener of 12.5 mm dia meter 50 mm length or suitable anchor fastener or metal screws with nylon plugs and the studs 48 mm wide having one flange of 34 mm and other flange 36 mm and 0.50 mm thick fixed vertically within flanges of floor and ceiling channel and placed at a spacing of 610 mm centre to centre by 6 mm dia bolts and nuts, including fixing of studs along both ends of partition fixed flush to wall with suitable anchor fastener or metal screws with nylon plugs at spacing of 450 mm centre to centre, and fixing of boards to both side of frame work by 25 mm long dry wall screws on studs, floor and ceiling channels at the spacing of 300 mm centre to centre.</p>			
---	--	--	--	--



<p>staggered to avoid through cracks, M.S. fixing channel of 99 mm width (0.9 mm thick having two flanges of 9.5 mm each) to be provided at the horizontal joints of two boards, fixed to the studs using metal to metal flat head screws, including jointing and finishing to a flush finish with recommended jointing compound, jointing tape, angle beads at corners (25 mm x 25 mm x 0.5 mm), joint finisher and two coats of primer suitable for board as per manufacturer's specification and direction of engineer in charge all complete. Quoted rates shall be including GST , labour, lead , lift , transportation etc complete. Nothing extra shall be paid separately.</p>		
<p>4.1 66mm overall thickness Partition with 8mm thick double skin Calcium Silicate Board made with Calcareous & Siliceous materials reinforced with cellulose fiber manufactured through autoclaving process with Compressive Strength 225 kg/sq.cm, Bending Strength 100 kg./ sq.cm.</p>	<p>Sqm 15.00</p>	
<p>4.2 Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade :Two or more coats on new work. Approved Make Asian/Burger/Nerolac. Quoted rates shall be including GST , labour, lead , lift , transportation etc complete. Nothing extra shall be paid separately.</p>	<p>Sqm 30.00</p>	
TOTAL		



(Signature)
N. Kulkarni

**EXECUTIVE ENGINEER
IISER PUNE**