



भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान, पुणे
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH PUNE

(An Autonomous Institution, Ministry of Human Resource Development, Govt. of India)

IISER Pune Campus, Dr. Homi Bhaba Road, Pune-411 008.

Ph No 020 2590 8001 Fax 020 2588 7499 / 2589 8022

No: /IISER/Pune/2017-18

Dated 1/9/2017

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to 3.00 PM on 11/9/2017 from approved and eligible contractors registered with CPWD, Maharashtra State PWD, Railways, MES in appropriate category for Civil/ (B&C) works for the work mentioned below. The quotations will be opened at 3.30 PM on the same day.

NAME OF WORKS : MISCELLANEOUS REPAIRS WORKS AT GYMNASIUM , WATER SUPPLY LINE TO FIELD PLOT & PAINTING WORKS AT IISER PUNE CAMPUS.

Issue to –

Name and address of the agency –

IISER Pune

Terms and Conditions:

- 1) The applicant should be registered with CPWD in western region, Maharashtra State PWD, MES, Railways in appropriate category for Civil/ (B & C) works. The registration certificate should be valid till the last date of receipt of tender. Applicant should submit attested or notarized copies of the registration certificate along with quotation.
- 2) Time period for completion of work shall be 7 (Seven) days from the date of placing the work order by IISER Pune. The act of backing-out after quotation will debar such agencies for participating in future quotations of IISER PUNE.
- 3) Quotation can be obtained from IISER PUNE Engineering office at Main Building between 10 AM to 4 PM on all working days before date of submission. Applicant may quote by downloading quotation document from IISER PUNE website.
- 4) All agencies need to submit their quotation in hard copy in a sealed envelope to this office by suitable means on and before 3 PM on 11/9/2017. Quotation received after the date & time specified above shall not be accepted. Any delays , postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ . The bid shall be submitted in the original bid document (as issued by the IISER, Pune) super scribing the name of work. Rates quoted in the words shall be treated as final.

- 5) Quotations will be opened on the same day at 3.30 PM in the presence of agency or their authorized representatives, if any. The offer of the agency should be commercially clear including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons.
- 6) Quotations submitted with any conditions shall be treated as conditional quotations and shall be summarily be rejected by IISER PUNE.
- 7) Quoted rates should be inclusive of cost of all the materials, labour cost , all taxes, octroi , duties , cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid separately.
- 8) All approved makes shall be as specified in BOQ and as per CPWD specifications , agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work.
The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location.
No advance payment shall be made by IISER Pune.
Quoted rates should be including GST , TDS and other applicable taxes and cess will be deducted from the bills of the work.
- 9) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER PUNE whenever specification CPWD/ IS specification are not available.
- 10) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws.
- 11) L1 Agency to submit actual measurements and abstract sheet to IISER PUNE within 30 days from completion of work.

IISER Pune

Encl : - Schedule of Quantity (BOQ) – As per Annexure A

Sign & stamp of Agency-

ANNEX-A : BILL OF QUNAITITY

NAME OF WORKS : MISCELLANEOUS REPAIRS WORKS AT GYMNASIUM , WATER SUPPLY LINE TO FIELD PLOT AND PAINTING WORKS AT IISER PUNE CAMPUS.

ITEM NO	DESCRIPTION	QUANTITY	UNIT	RATE IN WORDS AND FIGURES	AMOUNT
A	GYMNASIUM REPAIR WORKS				
1	Making the opening in brick masonry including dismantling in floor or walls by cutting masonry and making good the damages to walls, flooring and jambs complete, to match existing surface i/c disposal of mulba/ rubbish to the nearest municipal dumping ground, all complete as per directions of Engineer-In-Charge.For door/ window/ clerestory window.	1.20	sqm		
2	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	1.00	sqm		
3	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per directions of Engineer-In-Charge. With cement mortar 1:4 (1cement: 4 coarse sand).	1.00	sqm		
4	Providing & fixing 6mm thick first quality bevel edge , Modiguard mirror or equivalent approved make . Quoted rate shall be including removal of exising Brocken mirrors , lead and lift of mirror , fixing of mirror in existing fittings over existing plywood , sealing of joints by silicon sealant , disposal of damaged mirror within 500m etc complete. Nothing extra shall be paid separately.	25.00	Sqm		

NAME OF WORKS : MISCELLANEOUS REPAIRS WORKS AT GYMNASIUM , WATER SUPPLY LINE TO FIELD PLOT & PAINTING WORKS AT IISER PUNE CAMPUS.

5	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surfaces smooth including necessary repairs to scratches etc. complete.	250.00	sqm		
6	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : Old work (one or more coats). Quoted rate shall be including scrapping of old paint , necessary primer , putty , filling of cracks, sanding etc complete. Nothing extra shall be paid separately.	250.00	sqm		
7	Providing and fixing flat pressed 3 layer medium density particle board or graded particle board (Grade I) IS: 3087 marked, in wall/ceiling/boxing with necessary nails etc. complete (frame work to be paid separately): 12 mm thick.	20.00	sqm		
PEB Annex Earth Science Lab					
8	Providing & applying Luster paint of Asian/ Nerolac/Berger of low VOC as per manufacturers specifications on wall / ceiling with roller finish including preparation of surface , filling of cracks and touch-up works. Quoted rate shall be including smooth sanding, scaffolding , primer , putty , filling of cracks , all leads and lift, labour , cleaning and cost of all materials etc complete as per direction of Engineer-in-charge. (Nothing extra shall be paid separately) : For One and more coat.	200.00	Sqm		

NAME OF WORKS : MISCELLANEOUS REPAIRS WORKS AT GYMNASIUM , WATER SUPPLY LINE TO FIELD PLOT & PAINTING WORKS AT IISER PUNE CAMPUS.

B	RESEARCH FIELD PLOT WORKS				
9	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work				
9.1	50 mm dia nominal bore	100.00	meter		
9.2	25 mm dia nominal bore	5.00	meter		
9.3	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) : 50 mm nominal bore.	2.00	each		
9.4	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 50 mm nominal bore	1.00	each		
9.5	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 25 mm nominal bore	3.00	each		

NAME OF WORKS : MISCELLANEOUS REPAIRS WORKS AT GYMNASIUM , WATER SUPPLY LINE TO FIELD PLOT & PAINTING WORKS AT IISER PUNE CAMPUS.

9.6	Making connection of G.I. distribution branch with G.I. main of followingsizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 50 to 25 mm nominal bore.	1.00	each		
9.7	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete : 25 mm nominal bore	1.00	each		
D	SERVER ROOM AT FF CHEMISTRY				
10	Providing GI adjustable type pedestal of 300mm high with top flange and bottom adjustable base for making support structure of raised flooring.	400.00	each		
11	Providing GI screws of 40mm long 8mm diameter.	10.00	100 Nos		
		TOTAL			

Sign & stamp of Agency-

IISER PUNE