



भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान, पुणे
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH PUNE

(An Autonomous Institution, Ministry of Human Resource Development, Govt. of India)

IISER Pune Campus, Dr. Homi Bhabha Road, Pune-411 008.

Ph No 020 2590 8001 Fax 020 2588 7499 / 2589 8022

No: 54(2) /IISER/Pune/2019-20/

Dated 04/11/2019

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to **3.00 PM on 11/11/2019** from eligible contractors registered with anyone CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite category for the work mentioned below. The quotations will be opened at 3.30 PM on the same day.

NAME OF WORKS : PROVIDING EXTERNAL PAINTING TO PASHAN GATE , KERB STONE PAINTING AND MISC WORKS AT IISER PUNE.

Issue to –

Name and address of the agency –


Executive Engineer

Terms and Conditions:

- 1) The applicant should be eligible contractors registered with anyone CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite Category. Applicant should submit attested or notarized copies of the valid Registration Certificate and Experience Certificate along with the quotation. Bidders not meeting the minimum eligibility criteria shall be summarily rejected.
- 2) Time period for completion of work shall be **10 (Ten) days** from the date of placing the work order by IISER Pune. The act of backing-out after opening of quotation will debar such agencies for participating in the future quotations of IISER PUNE. Bidder may e-mail queries on maintenance@iiserpune.ac.in or submit to IISER PUNE office in hard copy on all working days one day before submission date of quotation as specified above.
- 3) Notice Inviting Quotation (NIQ) document may be obtained from IISER PUNE at 121, Engineering Section , Main Building, IISER PUNE Campus, Dr.Homi Bhabha Road, Pashan, Pune-411008 between 10 AM to 4 PM on all working days before date of submission. Applicant may submit quotation by obtaining NIQ document from IISER PUNE website at <http://www.iiserpune.ac.in/links/tender-notices-and-eoi>
- 4) All agencies need to submit their quotation in hard copy in sealed envelope containing by suitable means on and before **3 PM on 11/11/2019**. Quotation received after the date & time specified above shall not be accepted. Any delays , postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ . Rates quoted in words shall be treated as Final for deciding L1 bidder. The bid shall be submitted in the original bid document (as issued by the IISER, Pune or Webcopy) super scribing the name of work. Quoted rates shall be valid for 60 days from the date of opening of quotations. Rates shall be quoted in hand writing at the spaces provided in NIQ document. Commercial envelopes of technically qualified bidders shall be opened accordingly . The offer of the agency should be commercially clear including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons.

Sign & stamp of Agency-



NIQ : Page 1 of 5

- 5) Bids will be opened **on the same day at 3.30 PM** in the presence of agency or their authorized representatives, if any. Quotations submitted with any conditions shall be treated as conditional quotations and shall be summarily be rejected by IISER PUNE.
 - 6) Quoted rates should be inclusive of cost of all the materials, labour cost , GST ,all taxes, royalties, cost of fuel, operator , octroi , duties , cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid separately. No, Bidder shall contact the IISER, Pune on any matter relating to his bid from the time of the bid opening to the time of issue of work order. Any effort by the Bidder to influence the IISER's bid evaluation, bid comparison or contract award decisions, may result in the rejection of his bid. Decision from competent authority/Engineer In-charge shall be final and binding to bidder in all the matters relating this work.
 - 7) All approved makes shall be as specified in BOQ and as per CPWD specifications, agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work. The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location. Any scaffolding required shall be brought by contractor to complete the work with no cost to IISER Pune.
- No advance payment shall be made by IISER Pune. Quoted rates should be including GST , TDS and other applicable taxes . Income Tax and labour cess will be deducted from the bills of the work.
- 8) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER PUNE whenever specification CPWD/ IS specification are not available.
 - 9) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws. All the safety measured shall be followed by the L1 agency as per prescribed norms during execution of work with all the necessary safety tools etc. Executing Agency shall sole techno-commercially responsible for the strict adherence of safety norms and allied compensations etc.
 - 10) Agency should submit measurements and abstract sheets to IISER PUNE for the payments within 30 days from completion of work.


Executive Engineer

Encl : - Schedule of Quantity (BOQ) – As per Annexure A



Sign & stamp of Agency-

ANNEX-A: BILL OF QUANTITIES

NAME OF WORKS : PROVIDING EXTERNAL PAINTING TO PASHAN GATE , KERB STONE PAINTING AND MISC WORKS AT IISER PUNE.

SR NO	DESCRIPTION	Quantity	Unit	Rate in words and figures	Amount
1	Finishing walls with Acrylic Smooth exterior paint of required shade: Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing paint surface .Quoted rate shall be working at any height upto 20 Meter with all safety harness , safety rope , cleaning of algae/fungus black spots etc complete. Rate including of all taxes, duties, GST, nothing extra shall be payable)	3,000.00	sqm		
2	Painting of kerb stones by painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : two or more coats on concrete surface. Quoted rate shall be including cleaning of kerb stones , of all taxes, duties, GST, nothing extra shall be payable.	1000	Sqm		
2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : two or more coats on any surface/Pergola's. Quoted rate shall be working at any height upto 20 Meter with all safety harness , safety rope , cleaning of algae/fungus black spots etc complete. Rate including of all taxes, duties, GST, nothing extra shall be payable)	500	Sqm		



Sign & stamp of Agency-

3	<p>Repair works in polished granite flooring by removing existing unserviceable/ broken granite flooring, removal of base mortar , providing and laying similar shade and texture polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building, all complete as per the architectural drawings, with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand), laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade, including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge. Polished Granite stone slab Jet Black, Multi Red, Steel grey , sinduri red , Sadarhalli , Chikku Brown, or as approved bt Engineer In-charge. Quoted rate shall be including removing of existing unserviceable/cracked granite , disposing of debris at approved dumping ground within campus , providing and fixing new granite , including grouting with matching pigments as per instruction of Engineer In-charge , etc complete. Quoted rate shall be including GST , trasportation , lead , lift , wastage, scaffolding etc complete. Nothing extra shall be paid seperatly. Actual area of new granite laid at site shall be measured for payments. (Rate including of all taxes, duties, GST, nothing extra shall be payable)</p>	10	sqm
4	<p>Taking out existing kerb stones of all types from footpath/ central verge, including removal of mortar etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge. (Rate including of all taxes, duties, GST, nothing extra shall be payable)</p>	30	Mtr.



Sign & stamp of Agency-

6	<p>Providing & fixing testing, commissioning sensor urinals auto flushing urinal system with sensor, solenoid valve system with new functional automatic flushing system make Hindware, size 610x390x380mm model no. 60007, ceramic body including spare parts. Set containing 1. urinal sensor eye including battery box ceramic body Hindware Pot Model no.-60007 2. sensor solenoid valve 3. CP Discharge nozzle 4. SS 304 waste coupling with SS coupling dome & SS 304 Hindware bottle trap, 5. wall bracket 6. Connector pipe 1/2x1" (male female type) 7. 50x40mm PVC bushing 8. SS 304 top cover etc complete. A complete of accessories shall be provided. (Rate including of all taxes, duties, GST, nothing extra shall be payable)</p>	5	Each
7	<p>Providing and fixing at or near ground level precast cement concrete / Factory Made in kerb stones, edgings etc. as per approved pattern and setting in position with cement mortar 1:3 (1 Cement : 3 coarse sand), including the cost of required centering, shuttering complete. 4.6.1 1:1½:3 (1 Cement: 1½ coarse sand(zone-II) : 3 graded stone aggregate 20 mm nominal size).</p>	5	cum
8	<p>Replacing 6mm tinted glass by removal of existing brocked glasse , disposal of glass. Glass shall be fixed with external grade silicon sealant etc complete. Quoted rate shall be including GST , transportation , lead , lift , wastage, scaffolding etc complete. Nothing extra shall be paid separately.</p>	5	sqm
TOTAL			


Executive Engineer

