



भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान, पुणे  
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH PUNE

(An Autonomous Institution, Ministry of Human Resource Development, Govt. of India)

IISER Pune Campus, Dr. Homi Bhaba Road, Pune-411 008.

Ph No 020 2590 8001 Fax 020 2588 7499 / 2589 8022

No: 54(2) /IISER/Pune/2019-20/

Dated 7/10/2019

**NOTICE INVITING QUOTATION**

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to **3.00 PM on 16/10/2019** from approved and eligible contractors registered with CPWD, Maharashtra State PWD, Railways, MES in appropriate category for Civil/ (B&C) works for the work mentioned below. The quotations will be opened at 3.30 PM on the same day.

**NAME OF WORKS : REPAIRS TO KERB STONES, PAVERS , PAINTING TO KERB STONE AND EXTERNAL FAÇADE PAINTING OF GUEST HOUSE BUILDING AT IISER PUNE.**

Issue to –

Name and address of the agency –

  
Executive Engineer,

**Terms and Conditions:**

- 1) The applicant should be registered with CPWD in western region, Maharashtra State PWD, MES, Railways in appropriate category for Civil/ (B & C) works. The registration certificate should be valid till the last date of receipt of tender. Applicant should submit attested or notarized copies of the valid registration certificate along with quotation.
- 2) Time period for completion of work shall be 15 (Fifteen ) days from the date of placing the work order by IISER Pune. The act of backing-out after quotation will debar such agencies for participating in future quotations of IISER PUNE. Bidder may e-mail queries on [maintenance@iiserpune.ac.in](mailto:maintenance@iiserpune.ac.in) or submit to IISER PUNE office in hard copy on all working days before a day of submission date of quotation.
- 3) Quotation can be obtained from IISER PUNE Engineering office at Main Building between 10 AM to 4 PM on all working days before date of submission. Applicant may quote by downloading quotation document from IISER PUNE website.
- 4) All agencies need to submit their quotation in hard copy in a sealed envelope to this office by suitable means on and before **3 PM on 16/10/2019**. Quotation received after the date & time specified above shall not be accepted. Any delays , postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ . The bid shall be submitted in the original bid document (as issued by the IISER, Pune) super scribing the name of work. Rates quoted in the words shall be treated as final for deciding L1 bidder.

Sign and Seal of Agency

Page 1 of 4



- 5) Quotations will be opened on the **same day at 3.30 PM** in the presence of agency or their authorized representatives, if any. The offer of the agency should be commercially clear including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons.
- 6) Quotations submitted with any conditions shall be treated as 'Conditional Quotation' and shall be summarily be rejected by IISER PUNE.
- 7) Quoted rates should be inclusive of cost of all the materials, labour cost , GST , all taxes, octroi , duties , cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid separately.
- 8) All approved makes shall be as specified in BOQ and as per CPWD specifications , agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work.  
The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location.  
No advance payment shall be made by IISER Pune. Quoted rates should be including GST, TDS and other applicable taxes and cess will be deducted from the bills of the work as applicable.
- 9) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER PUNE whenever specification CPWD/ IS specification are not available.
- 10) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws.
- 11) L1 Agency to submit actual measurements and abstract sheet to IISER PUNE within 30 days from completion of work.

  
**Executive Engineer,**  
**IISER Pune**

Encl: - Schedule of Quantity (BOQ) – As per Annexure



Sign and Seal of Agency  
Page 2 of 4

**BILL OF QUANTITY**

**NAME OF WORKS : REPAIRS TO KERB STONES, PAVERS , PAINTING TO KERB STONE AND EXTERNAL FAÇADE PAINTING OF GUEST HOUSE BUILDING AT IISER PUNE.**

SR NO	DESCRIPTION	Quantity	Unit	Rate in words and figures	Amount
1	Finishing walls with Acrylic Smooth exterior paint of required shade: 14.66.1 Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing paint surface. Quoted rate shall be working at any height upto 20 Meter with all safety harness , safety rope , GST, cleaning of algie/fungus black spots etc complete.	2,700.00	sqm		
2	Finishing walls with Acrylic Smooth exterior paint of required shade: Old work (One or more coat applied @ 0.90 ltr/10 sqm) Quoted rate shall be working at any height upto 20 Meter with all safety harness , safety rope , GST, cleaning of algie/fungus black spots etc complete.	2,700.00	sqm		
3	Painting of kerb stones with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work. Quoted rate shall be including at taxes , duties , royalties , primer, lead, lift , transportation , insurance , GST , etc. Nothing extra shall be paid seperatly. Shade and scheme shall be got approved from Engineer In-charge before taking-up work. Approved Makes Nerolac/Dulux/Asian. Quoted rate shall be with all safety harness , safety rope , cleaning of algie/fungus black spots etc complete.	1000	Sqm		
4	Repair and relaying of existing CC interlocking paver blocks from footpath/ central , verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, stacking of serviceable material within 50 metre lead , relaying on layer of 20mm sand , fixing using mortar of 1:4 as per direction of Engineer-in-Charge. etc complete.	100	sqm		



Sign and Seal

5	Repairs to old kerb stones of all types in position , to the required line, level and curvature, jointed with cement mortar , 1:3 (1 cement : 3 coarse sand), including making joints with or without , grooves (thickness of joints, except at sharp curve, shall not be more than 5 mm), including making drainage opening wherever required etc. complete as per direction of Engineer-in-charge. (Length of finished kerb edging shall be measured for payment). (All existing kerb stones shall be used , casting of new kerb stone shall be paid separately) metre 82.95	100	meter	
6	extra for providing new CC interlocking paver for Item No-4	25	sqm	
7	extra for providing new CC kerb stone in M25 matching to existing pattern for including cost of shuttering , concrete etc item No-5	2	cum	
<b>TOTAL</b>				



  
 EXECUTIVE ENGINEER