



भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान, पुणे
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH PUNE

(An Autonomous Institution, Ministry of Human Resource Development, Govt. of India)

IISER Pune Campus, Dr. Homi Bhabha Road, Pune-411 008.

Ph No 020 2590 8001 Fax 020 2588 7499 / 2589 8022

No: 54(2) /IISER/Pune/2020-21/09

Dated 26/05/2020

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to **3.00 PM on 2/06/2020** from eligible contractors registered with anyone CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite category (any one) for the work mentioned below. The quotations will be opened at 3.30 PM on the same day.

NAME OF WORK- REPAIRING AND LAYING OF GI PIPE LINE FOR LANDSCAPE GRID FROM SEWAGE TREATMENT PLANT (STP) LINE AT IISER PUNE.

Issue to –

Name and address of the agency –



N. Kulkarni

Executive Engineer

Terms and Conditions:

- 1) The applicant should be eligible contractors registered with anyone CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite Category or Specialized agencies associated with water supply/plumbing works. Applicant should submit attested or notarized copies of the valid Registration Certificate and Experience Certificate along with the quotation. Bidders not meeting the minimum eligibility criteria shall be summarily rejected.
- 2) Time period for completion of work shall be 07 days from the date of placing the work order by IISER Pune. The act of backing-out after opening of quotation will debar such agencies for participating in the future quotations of IISER PUNE. Bidder may e-mail queries on maintenance@iiserpune.ac.in or submit to IISER PUNE office in hard copy on all working days one day before submission date of quotation as specified above.
- 3) Notice Inviting Quotation (NIQ) document may be obtained from IISER PUNE at 121, Engineering Section , Main Building, IISER PUNE Campus, Dr.Homi Bhabha Road, Pashan, Pune-411008 between 10 AM to 4 PM on all working days before date of submission.

Sign & stamp of Agency-

NIQ : Page 1 of 7

Applicant may submit quotation by obtaining NIQ document from IISER PUNE website at <http://www.iiserpune.ac.in/links/tender-notices-and-eoi>

- 4) All agencies need to submit their quotation in hard copy in sealed envelope containing by suitable means on and before **3 PM on 2/06/2020**. Quotation received after the date & time specified above shall not be accepted. Any delays , postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ . Rates quoted in words shall be treated as Final for deciding L1 bidder. The bid shall be submitted in the original bid document (as issued by the IISER, Pune or Webcopy) super scribing the name of work. Quoted rates shall be valid for 60 days from the date of opening of quotations. Rates shall be quoted in hand writing at the spaces provided in NIQ document. Commercial envelops of technically qualified bidders shall be opened accordingly . The offer of the agency should be commercially clear including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons.
- 5) Bids will be opened **on the same day at 3.30 PM** in the presence of agency or their authorized representatives, if any. Quotations submitted with any conditions shall be treated as conditional quotations and shall be summarily be rejected by IISER PUNE.
- 6) Quoted rates should be inclusive of cost of all the materials, labour cost , GST ,all taxes, royalties, cost of fuel, operator , octroi , duties , cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid separately. No, Bidder shall contact the IISER, Pune on any matter relating to his bid from the time of the bid opening to the time of issue of work order. Any effort by the Bidder to influence the IISER's bid evaluation, bid comparison or contract award decisions, may result in the rejection of his bid. Decision from competent authority/Engineer In-charge shall be final and binding to bidder in all the matters relating this work.
- 7) All approved makes shall be as specified in BOQ and as per CPWD specifications, agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work. The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location. Any

Sign & stamp of Agency-



scaffolding required shall be brought by contractor to complete the work with no cost to IISER Pune.

- 8) No advance payment shall be made by IISER Pune. Quoted rates should be including GST , TDS and other applicable taxes . Income Tax and labour cess will be deducted from the bills of the work.
- 9) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER PUNE whenever specification CPWD/ IS specification are not available.
- 10) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws. All the safety measures shall be followed by the L1 agency as per prescribed norms during execution of work with all the necessary safety tools etc. Executing Agency shall be sole techno-commercially responsible for the strict adherence of safety norms and allied compensations etc.
- 11) Agency should submit measurements and abstract sheets to IISER PUNE for the payments within 30 days from completion of work.



Executive Engineer

Encl : - Schedule of Quantity (BOQ) – As per Annexure A



ANNEX-A : Bill Of Quantity

NAME OF WORK- REPAIRING AND LAYING OF GI PIPE LINE FOR LANDSCAPE GRID FROM SEWAGE TREATMENT PLANT (STP) LINE AT IISER PUNE.

Sr No	Description of Item	Unit	Qty.	Rate in words and Figures	Amount in words and Figure
1	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 meter lead as per direction of Engineer-in-Charge. (Rate including of all taxes, duties, material, labour, wastage, nothing extra shall be payable)	Sqm	20		
2	Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, color and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineering- charge. (Old CC paver blocks shall be supplied by the department free of cost). (Rate including of all taxes, duties, material, labour, wastage, nothing extra shall be payable)	Sqm	20		
3	Removing & Laying at or near ground level old kern stones of all types in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement : 3 coarse sand), including making joints with or without grooves (thickness of joints, except at sharp curve, shall not be more than 5 mm), including making drainage opening wherever required etc. complete as per direction of Engineer-in-charge. (Length of finished kern edging shall be measured for payment). (Rate including of all taxes, duties, material, labour, wastage, nothing extra shall be payable)	Mtr.	20		



Sign & stamp of Agency-

NIQ : Page 4 of 7

Sr No	Description of Item	Unit	Qty.	Rate in words and Figures	Amount in words and Figure
4	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil. (Rate including of all taxes, duties, material, labour, wastage, nothing extra shall be payable)	Cum	250		
5	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead up to 50 m and lift up to 1.5 m, as directed by Engineer-in charge. Ordinary rock (Rate including of all taxes, duties, material, labour, wastage, nothing extra shall be payable)	Cum	5		
6	Dismantling of C.I. sluice valve including stacking of useful materials within a lead of 50 metres Up to 150 mm diameter. (Rate including of all taxes, duties, material, labour, wastage, nothing extra shall be payable)	Each	1		
7	Providing & laying GI pipe 100 mm dia grade B class Jindal make or equivalent with required specials bend, tee, sockets, fittings, etc Complete. Piping shall be done in flanged pipe/socketed pipe as per site conditions. Quoted rate shall be including cost of flange-bolt-gasket/socket. At turning pipe shall be bend to required profile (Rate including of GST, all taxes, duties, material, labour, wastage, nothing extra shall be payable). Actual pipe laid at site shall be measured for payments.	Mtr.	110		

Sign & stamp of Agency-

NIQ : Page 5 of 7



Sr No	Description of Item	Unit	Qty.	Rate in words and Figures	Amount in words and Figure
8	Providing & Fixing GI union 100mm dia to G.I. Union including cutting and threading the pipe and making long screws etc. complete (New work) : (Rate including of GST, all taxes, duties, material, labour, wastage, nothing extra shall be payable). Actual fitting at site shall be measured for payments.	Each	2		
9	Making connection in water line from DI Line to GI line with required fittings, flanges, bolts, cutting of pipe, fixing of flanges, rubber gasket, nut bolts, etc complete the job. (Rate including of GST, all taxes, duties, material, labour, wastage, nothing extra shall be payable). Actual work done at site shall be measured for payments.	Job	2		
10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size). (Rate including of GST, all taxes, duties, material, labour, wastage, nothing extra shall be payable).	Cum	3		
11	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete up to plinth level. Mild steel and Medium Tensile steel bars (Rate including of GST, all taxes, duties, material, labour, wastage, nothing extra shall be payable).	Kg	30		
12	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately) : 100 mm diameter Class II (Rate including of GST, all taxes, duties, material, labour, wastage, nothing extra shall be payable).	Each	4		



Sr No	Description of Item	Unit	Qty.	Rate in words and Figures	Amount in words and Figure
13	Constructing masonry Chamber 120x120x100 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for sluice valve, with C.I. surface box 100 mm top diameter, 160 mm bottom diameter and 180 mm deep (inside) with chained lid and RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) , i/c necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick, finished with a floating coat of neat cement complete as per standard design : With common burnt clay F.P.S.(non modular) bricks of class designation. (Rate including of GST, all taxes, duties, material, labour, wastage, nothing extra shall be payable).	Each	1		
14	Providing and laying red agra stone of required size and shape of approved shade, color and texture in footpath, flooring cut granite stone of required size and shape of approved shade, color and texture in footpath, flooring in road side plazas and similar locations, laid over 20mm thick base of cement mortar 1:4 (1cement : 4 coarse sand) including grouting the joints with white cement mixed with matching pigment, epoxy touch ups etc. complete as per direction of Engineer-in-Charge. (Red Agra Stone available at store free of cost) (Rate including of GST, all taxes, duties, material, labour, wastage, nothing extra shall be payable).	Job	1		
TOTAL AMOUNT					

Akshay

EXECUTIVE ENGINEER, IISER Pune



